

LAW QUARRY EXTENSION

PORT COLBORNE, ONTARIO

AIR QUALITY ASSESSMENT

RWDI #2202166

February 3, 2022

SUBMITTED TO

Ed Lamb

elamb@waterfordgroup.ca

Waterford Sand & Gravel Limited

70 Ewart Avenue
Brantford, ON N3T 5M1

T: 519.752.1300 ext. 124

M: 519.500.8146

SUBMITTED BY

Monika Greenfield, M.Sc.

Senior Project Manager, Strategic Advisor

Monika.Greenfield@rwdi.com

Brian G. Sulley, B.A.Sc.

Technical Director, Principal

Brian.Sulley@rwdi.com

RWDI

600 Southgate Drive
Guelph, ON N1G 4P6
T: 519.823.1311



TABLE OF CONTENTS

1	INTRODUCTION	1
2	SITE DESCRIPTION & OPERATIONS.....	1
3	OPERATING SCENARIO	2
4	SENSITIVE IMPACT LOCATIONS.....	2
5	CONTAMINANTS AND SOURCES CONSIDERED	3
6	EMISSION ESTIMATION	4
7	DISCUSSION OF MITIGATION MEASURES	4
8	DISPERSION MODELLING	5
9	LOCAL EMISSION SOURCES.....	6
10	BACKGROUND AIR QUALITY DATA.....	7
11	RECOMMENDATIONS FOR SITE PLAN	8
12	RECOMMENDED MANAGEMENT PRACTICES.....	9
13	CONCLUSIONS	9

LIST OF TABLES

Table 1:	Ambient Air Quality Data
Table 2:	Cumulative Effects Analysis with Mitigation – Phase 1A
Table 3:	Cumulative Effects Analysis with Mitigation – Phase 1B
Table 4:	Cumulative Effects Analysis with Mitigation – Phase 2
Table 5:	Cumulative Effects Analysis with Mitigation – Phase 3



LIST OF FIGURES

Figure 1:	Phases of Extraction, License Boundary, Additional Lands & Receptor Location
Figure 2A:	Locations of Sources – Asphalt Plant
Figure 2B:	Locations of Sources – Phase 1a
Figure 2C:	Locations of Sources – Phase 1b
Figure 2D:	Locations of Sources – Phase 2
Figure 2E:	Locations of Sources – Phase 3
Figure 3:	Locations of Sources – Reeb Quarry

LIST OF APPENDICES

Appendix A:	Blasting Operations Emission Spreadsheet
Appendix B:	Processing Emissions Spreadsheet
Appendix C:	Bulk Material Handling Emission Spreadsheet
Appendix D:	On-Site Mobile Equipment Emissions Spreadsheet - Fugitive Dust
Appendix E:	Combustion Exhaust Emissions (Mobile and Stationary Sources)
Appendix F:	Summary of Additional Emissions from Asphalt Plant



REPORT SIGNATURES

A handwritten signature in black ink, appearing to read 'B. Sulley', written over a horizontal line.

Brian G. Sulley, B.A.Sc., P.Eng.



1 INTRODUCTION

RWDI was retained by Waterford Sand & Gravel Limited to conduct an air quality assessment for the proposed Law Quarry Extension (the Quarry) in Port Colborne, Ontario. The facility is applying for a Class A license, with an annual extraction limit of 800,000 tonnes per year. This air quality assessment provides an estimate of emissions from expanded operations at the Quarry, and a prediction of impacts due to those emissions on nearby sensitive impact locations through a dispersion modelling analysis. The predicted impacts are then compared against the relevant provincial or federal air quality criteria. If predicted impacts are above the relevant criteria at nearby sensitive impact locations, mitigation measures are recommended, and the assessment is repeated. This process continues until predicted impacts are below the criteria. The mitigation measures are incorporated into the Best Management Practices Plan (BMPP) for dust.

2 SITE DESCRIPTION & OPERATIONS

The existing Quarry and the proposed extension are aggregate operations, to be operated under a Class A license (quarry operations with excavation below the water table) under the Aggregate Resources Act (ARA). The proposed extension will take place on the lands to the west of the existing Quarry, between Bierderman Rd. and Graybiel Rd., north of Highway 3. Operations in the proposed extension are expected to be similar to those at the existing Quarry. The site entrance will remain at the current location. The existing operations also include crushing of recycled concrete and asphalt, which is accounted for in the overall air quality assessment.

Operations at the proposed extension will consist of drilling, blasting, extraction of aggregate via front-end loader, processing, transportation, washing, stockpiling, and shipping of finished aggregate, all with a maximum daily capacity of 8,000 tonnes per day. The North American Industrial Classification System (NAICS) code for the facility is 212315, Dolostone Mining and Quarrying.

It is our understanding that there are archaeological features on the site that create exclusion areas for extraction. These areas were provided to RWDI by MHBC Planning and are reflected in the assessment and shown on the attached figures.

The Miller Paving Limited hot-mix asphalt (HMA) plant is located on the southeast side of the existing Quarry property and although not part of the expansion, will be included for the assessment of like-contaminants, i.e., only emissions of contaminants that are in common with the proposed extension and the existing Quarry will be considered.

3 OPERATING SCENARIO

The maximum operating scenario examined in the assessment reflects the maximum production and shipping operations at the site, based on the peak day in the peak year over the entire life of the Quarry. This scenario is meant to provide a conservative estimate of potential air emissions. Operations would realistically occur at levels below these levels over most of the life of the Quarry. Operations during the winter months are normally much lower than during the construction season and have been reduced to 50% of maximum operations for the months of November through to February, inclusive.

Emissions associated with overburden stripping and berm construction are not examined explicitly in the assessment. These are considered short-term construction activities and are not part of the maximum operating scenario used in the assessment. Impacts associated with overburden stripping and berm construction are best managed through the development and implementation of the BMPP for dust. These controls will help to ensure that localized impacts due to the overburden stripping and berm construction are minimized, especially when they are occurring in close proximity to potential receptors.

In addition, the inclusion of fugitive dust from storage piles in the assessment of emissions and dispersion modelling is ineffective and often inaccurate. It is for this reason that the Ontario Ministry of Environment Conservation and Parks (MECP) prefers that applicants for Environmental Compliance Approvals (ECAs) at aggregate sites focus their efforts on developing BMPPs to deal with these sources, rather than conduct modelling exercises of little value. Modelling is not required in order to properly design control measures for these sources. RWDI believes that the mitigation measures in the BMPP are appropriate and that they will provide a suitable level of protection, as supported by our experience at numerous aggregate sites throughout Ontario.

Figure 1 provides a map showing the phases of extraction, license boundary, additional lands, and receptor locations.

4 SENSITIVE IMPACT LOCATIONS

In the area surrounding the proposed extension and the existing Quarry, there are two churches and several residences and receptor locations, as shown on **Figure 1**. Due to the nature of the sources of emissions, receptors located further from the site were not assessed, as impacts decrease rapidly with distance.

5 CONTAMINANTS AND SOURCES CONSIDERED

The primary contaminant of interest is airborne dust generated by operations at the site. The following key components of dust were modelled:

- Suspended particulate matter, which consists of particles with an aerodynamic diameter of 44 micrometres (μm) or less (known as TSP);
- Inhalable particulate matter, which consists of particles with an aerodynamic diameter of 10 micrometres (μm) or less (known as PM_{10});
- Respirable particulate matter, which consists of particles with an aerodynamic diameter of 2.5 μm or less (known as $\text{PM}_{2.5}$); and,
- Crystalline silica within the PM_{10} portion of the dust.

In addition to dust, on-site vehicles and heavy equipment also emit products of combustion. Nitrogen dioxide gas (NO_2), TSP, PM_{10} , and $\text{PM}_{2.5}$ were modelled as the key representatives of combustion products.

The potential sources of emissions in the proposed extension and the existing Quarry are as follows:

- Overburden stripping and rehabilitation operations (does not occur during worst case operation conditions and considered insignificant);
- Drilling;
- Blasting;
- Extraction and stockpiling of shot rock from the muck pile;
- Material handling operations (loading haul trucks, dumping material at the primary crusher, and loading highway trucks for shipping; transport of material to wash station);
- Material crushing, screening; and stockpiling;
- Equipment travel over unpaved surfaces (front end loaders and highway trucks);
- Tailpipe emissions from on-site vehicles and heavy equipment; and,
- Delivery, handling and processing of reclaimed concrete and reclaimed asphalt pavement (RAP).

As mentioned above, the Miller Paving HMA plant was also considered as an additional source of particulates, crystalline silica and NO_2 . The following activities were considered when determining the potential impact of the proposed Quarry in combination with the operations at this asphalt plant:

- Delivery of aggregates for use in the HMA plant;
- Handling of aggregates at the HMA plant cold feed bins;
- Operation of the HMA plant itself (aggregate dryer dust collector, silo filling, loadout to trucks);
- Equipment travel over unpaved surfaces to, at and from the asphalt plant (front end loaders and highway trucks); and,
- Tailpipe emissions of equipment associated with the asphalt plant.

Figures 2A to 2E show the representative source locations for operations in different phases of the project.



6 EMISSION ESTIMATION

Emissions were estimated in accordance with relevant guidance, using published emission factors. Detailed emission calculations are provided in **Appendix A to F**, inclusive. The appendices contain details on assumptions, equipment types, sample calculations and other details that provide clarity as to RWDI's methodology. Emissions from sources that are wind-speed dependent (e.g., material handling) were calculated on an hour-by-hour basis, using the wind speed for each hour in the meteorological record (taken from the meteorological files used for the AERMOD compliance modelling). The emission values shown in the appendices for the wind-speed dependent emissions sources are example values, based on the average wind speed from the meteorological data (in the actual analysis, there are more than 40,000 separate emission rates for each material handling source).

Emissions from the Miller Paving HMA Asphalt Plant were based on information from the 2020 AERMOD Compliance Assessment (ECA Number 8-2129-78-087) with some additional calculations for wind dependency, TSP size fraction, and additional contaminants not covered in the original assessment.

Four different operating scenarios over the course of operations were determined in consultation with Waterford Sand & Gravel Limited, consisting of extraction from various phases within the Quarry. Mitigation measures recommended in this assessment have been incorporated into a dust BMPP for the site. The emission estimates used in the final assessment account for the effects of these dust mitigation measures, such as watering of haul roads, and use of spray bars on processing equipment.

7 DISCUSSION OF MITIGATION MEASURES

The volume of truck and heavy equipment movement on unpaved surfaces within the proposed extension and existing Quarry require an above-average level of control, especially when operations move within 300m of sensitive receptors.

The 95% level of control used in the assessment for dust on the internal haul route is an outcome of the modelling, not an input assumption requiring justification. It represents the level of control found to be needed to achieve acceptable results at the nearest receptors. Published studies show that it is achievable. Rosbury (1985)¹ summarized results from various studies showing that levels of control as high as 98% were attained in some cases. Rosbury went on to prescribe a watering rate that would achieve near 100% control (approximately 1.7 L/m²/h). The U.S. EPA (AP-42, Chapter 13.2.2) showed that by maintaining a road surface moisture level of five times that of the ambient soil, a 95% level of control could be achieved. It is clear, therefore, that the 95% level of control prescribed by RWDI is attainable through sufficient watering. This finding of the studies is consistent with RWDI's experience in observing the effect of intensive watering programs.

Beginning with the wash screen, the wash plant processes and loading of washed product into trucks for shipment are considered insignificant. This reflects the washing process, in which the material is saturated with water, leading to no significant emissions of particulate. Handling of the washed product is also considered

¹ Rosbury, Keith D. "Dust Control at Hazardous Waste Sites". Hazardous Waste Engineering Research Laboratory, Office of Research and Development, U.S. EPA. EPA/540/2-85/003,



insignificant due to the absence of silt in the material. The moisture content of this product is often much higher as well, as some of the moisture from the washing process is retained. The MECP has accepted this approach for Environmental Compliance Approval (ECA) applications, and in their review of assessments conducted as part of applications under the ARA. This approach is consistent with the approach used in other jurisdictions as well. A review of available literature (e.g., San Joaquin Valley Air Pollution Control District, University of Minnesota, Golder) shows a similar approach in other jurisdictions.

The dispersion modelling analysis reflects the implementation of the controls described in Section 12.

8 DISPERSION MODELLING

Dispersion modelling was conducted to confirm that the proposed mitigation measures will be sufficient to control off-site impacts at the sensitive impact locations. The modelling was conducted in accordance with MECP Guideline A11: Air Dispersion Modelling Guideline for Ontario, using the U.S. EPA AERMOD v.19191 dispersion model. AERMOD assesses multiple sources of emissions at discrete off-site receptors or sensitive impact locations and is the current state-of-the-art regulatory model in Ontario.

Regional meteorological data obtained from the MECP website were used within the model, in accordance with the MECP's Guideline A11. Terrain information for the site was also obtained from the MECP website, in accordance with Guideline A11, but base elevations for sources within the site reflect the appropriate elevations shown in the Site Plans.

The model was run using the regulatory default options. The AERMOD model produced 1-hour, 24-hour, and annual average concentrations, as appropriate for each contaminant. The Oxygen Limiting Method (OLM) was used to convert NO_x to NO₂, and maximum O₃ concentrations were conservatively assumed.

Handling and processing sources were generally modelled as volume sources, in accordance with guidance from the National Stone Sand and Gravel Association (NSSGA)². Haul routes and heavy equipment movement were modelled using adjacent volume sources, in accordance with guidance from the MECP and NSSGA. Point sources were modelled using the appropriate source parameters.

² National Stone Sand and Gravel Association, "Modeling Fugitive Dust Sources with AERMOD", January 2007.

9 LOCAL EMISSION SOURCES

Environment Canada's National Pollutant Release Inventory (NPRI) is Canada's legislated, publicly accessible inventory of pollutant releases. Data for 2017 (the most recent available at the time of this report) were reviewed for locally significant emission sources that would have similar emission contaminants. There are several facilities that report PM and NO₂ in Port Colborne. While these facilities lie within 5km of the eastern fence line of the facility, impacts from these sites are not expected to significantly influence the predicted impacts from the extension.

Aerial photography for the area was also reviewed, along with the Ministry of Natural Resources and Forestry (MNR) Pits and Quarries Online tool and the MECP Access Environment tool for any registration on the Environmental Activity and Sector Registry (EASR) and ECAs for facilities in the area. The following sites are located within proximity to the facility, but do not report emissions to the NPRI:

- Reeb Quarry licenced to QBJR Aggregates Inc. (ALPS ID 607721), located due south of the current existing Quarry on the south side of Highway 3. This site is not currently in operation;
- Kwik-Mix Materials Limited (ERA-3106-8GGSAJ), located east of the Asphalt plant on Kwik Mix Rd.; and,
- Additional industrial facilities in Port Colborne with ECAs or EASR registrations, for equipment such as standby generator sets, welding operations, paint spray booths, or other smaller sources.

With the exception of Reeb Quarry, the impact from these sources is relatively small at the point of impact and RWDI believes that the adoption of a suitable background air quality level will provide a suitable estimate of cumulative impacts. Ambient background air quality for the region is provided in **Table 1**.

The Vale facilities in Port Colborne are located approximately 5km from the project site. Based on a review of the publicly available ECAs for the Vale facility, it was noted that the Vale site had no sources greater than 30 metres in height, and therefore impacts are expected to be highest near the facility and will decrease rapidly with distance. It is not expected that emissions from the Vale facility would pose any significant cumulative effect with the emissions from the proposed extension and existing Quarry.

Although not currently in operation, potential impacts from Reeb Quarry were included in the assessment explicitly because it is a licensed operation. Site Plans for Reeb Quarry were obtained from the MNR and reviewed in order to inform this assessment. The Site Plans do not indicate that an air quality assessment was prepared for the Reeb Quarry, however Condition 12 on the Operations Plan for the Reeb Quarry Site Plans states that:

"Dust will be controlled on site in accordance with applicable Ministry of Environment regulations and guidelines. Dust shall be mitigated and controlled by the use of spray bars located on contact points, conveyors and transfer points and through the use of water trucks, on internal haul roads and operation areas."



RWDI has therefore assumed that the Reeb sources have similar controls as those required at the proposed Quarry, which are described in Section 12. This includes a restriction on operations within 300 metres of a residence. As a simplification, emissions are therefore assumed to be similar between the two sites. Since RWDI does not have specific equipment locations for Reeb Quarry, an area source approach was used, as shown on the map provided in **Figure 3**.

10 BACKGROUND AIR QUALITY DATA

This assessment considered the impact of emissions from the proposed extension and existing Law Quarry in combination with background contaminant levels from other sources in the surrounding area. There are no air quality monitoring stations with publicly available data in close proximity to the site. Data from stations in the MECP monitoring network were reviewed, with a focus on the stations nearest to the site, and stations that may reflect a similar level of land use patterns and regional air quality sources.

MECP Station 27067 in St. Catharines is the nearest MECP monitoring station to the site. A review of stations with similar land use profiles to the area around the proposed extension and existing Quarry show results that are similar to or lower than those from the St. Catharines station. Background values were therefore assumed using data from the St. Catharines station.

Table 1 summarizes air quality background data used to characterize conditions in the study area. TSP and PM₁₀ were estimated from station-measured PM_{2.5} data using factors derived from the analysis of extensive monitoring data from other sites, as presented by the 2004 report by Lall et. al.³. Silica was estimated using published data for cities in the northeast U.S.⁴.

The 90th percentile concentration from the background monitoring data was used in the cumulative effects assessment. This represents the highest background concentration that could reasonably be expected to coincide with maximum impacts from existing operations in the area and the proposed extension and existing Law Quarry.

³ Lall, R., M. Kendall, K. Ito, and G. D. Thurston (2004). Estimation of Historical Annual PM_{2.5} Exposures for Health Effects Assessments, *Atmos. Env.*, 38, pp. 5217-5226.

⁴ United States Environmental Protection Agency (1996). Ambient Levels and Noncancer Health effects of Inhaled Crystalline Silica and Amorphous Silica: Health Issue Assessment. EPA/600/R-95-115.



11 RECOMMENDATIONS FOR SITE PLAN

The Quarry must operate in accordance with the operating standards pertaining to dust outlined in section 0.12 (2) Ontario Regulation 244/97, which include:

- The licensee or permittee shall apply water or another provincially approved dust suppressant to internal haul roads and processing areas, as necessary to mitigate dust, if the pit or quarry is located within 1,000 metres of a sensitive receptor.
- The licensee or permittee shall equip any processing equipment that creates dust with dust suppressing or collection devices if it is located within 300 metres of a sensitive receptor.
- The licensee or permittee shall obtain an environmental compliance approval under the Environmental Protection Act where required to carry out operations at the pit or quarry.

Furthermore, this assessment is based on the following recommendation, which is to be included on the Site Plans:

- The site will operate in accordance with a Best Management Practices Plan for fugitive dust (BMPP), which may be amended from time to time, considering actual impacts and operational considerations. The recommendations in the BMPP are based on the maximum daily production rates. At lower production rates, the control measures specified in the BMPP can be reduced accordingly, provided dust remains mitigated on site.



12 RECOMMENDED MANAGEMENT PRACTICES

RWDI recommends the following mitigation measures to be incorporated into the BMPP:

- A BMPP for the proposed extension and the existing Quarry will be developed with control measures capable of providing the emission reductions used in this assessment, including, but not limited to:
 - The portable processing plant shall not be located within 300m of a sensitive receptor, as shown on the attached figures;
 - When extraction operations move to within 300m of a sensitive receptor (the Portable Plant Exclusion and Enhanced Control Zone), as shown on the attached figures:
 - Blasting operations shall be allowed only when winds are blowing interior to the Quarry, or with a reduced blast area; and,
 - Extraction operations shall be curtailed as required to prevent visible dust from migrating to the sensitive receptor.
 - If a sensitive receptor property is purchased by Waterford Group, the 300-metre Portable Plant Exclusion and Enhanced Control Zone associated with that receptor location is no longer necessary.

RWDI also notes that the following mitigation measures have already been implemented at the existing operation:

- Paving of the main shipping haul route from the floor of the existing Quarry to the site entrance (a distance of approximately 300m), including all travelled areas around the scale house;
- Paving of the main shipping haul route for the Brennan Paving HMA plant; and,
- Contact with a third-party to conduct wet/vacuum sweeping of all paved areas as required to minimize buildup of surface silt and track-out onto the public roadway.

13 CONCLUSIONS

Tables 2 through 5 provide the results of the cumulative effects analyses at the closest receptors of interest, for the 4 operations scenarios considered. The results indicate that, with an appropriate BMPP for the site in place, concentrations at the nearby receptors are predicted to be at or below the relevant criteria for all contaminants 99.9% of the time during all phases. The results of the analysis demonstrate that the proposed Quarry extension has been appropriately designed, managed, and separated from surrounding sensitive land uses to prevent and mitigate adverse effects.

**AIR QUALITY ASSESSMENT
LAW QUARRY EXTENSION**

RWDI#2202166
February 3, 2022



RWDI aims to accommodate. If you require this document in a different format in order to aid accessibility, please contact the sender of this document, email solutions@rwdi.com or call +1.519.823.1311

TABLES




Table 1: Ambient Air Quality Data ^[1]

RWDI# 2202166

Year	TSP ^[2]		PM ₁₀ ^[2]	Silica	PM _{2.5}		NO ₂ ^[4]				O ₃ ^[4]	
	90th Percentile 24-hour (µg/m ³)	Annual Average (µg/m ³)	90th Percentile 24-hour (µg/m ³)	90th Percentile 24-hour ^[3] (µg/m ³)	90th Percentile 24-hour (µg/m ³)	Annual Average (µg/m ³)	90th Percentile 1-Hour		90th Percentile 24-hour		99th Percentile 1-Hour	
							(ppb)	(µg/m ³)	(ppb)	(µg/m ³)	(ppb)	(µg/m ³)
2016	43	21	24	1.4	13	6.3	14	28	11.1	22	64	132
2017	43	23	24	1.4	13	6.8	14	28	11.7	23	59	122
2018	47	23	26	1.6	14	6.9	12	24	10.1	20	61	126
2019	47	23	26	1.6	14	6.9	12	24	10.5	21	56	116
2020	40	21	22	1.3	12	6.3	10	20	8.9	18	60	124
Average	44	22	24	1.5	13	6.6	12	25	11	21	60	124

Notes:

[1] All data from MECP Station 27067 in St.Catharines, Ontario

[2] Estimated from PM_{2.5} measurements using published factors (Lall et al., 2004)

[3] Estimated as 6% of PM₁₀, from published data for cities in the northeast US (U.S. EPA, 1996)

[4] Conversion from ppb to µg/m³ based on 10°C

Table 2: Cumulative Effects Assessment - Operations in Phase 1A
 Modelled Values & Frequency of Excursions above the Relevant Criteria

RWDI# 2202166

Days of Valid Meteorological Data

1745

Relevant Criteria:

TSP	120	µg/m³ 24-Hour AAQC
	60	µg/m³ Annual AAQC
PM ₁₀	50	µg/m³ Interim AAQC
PM _{2.5}	27	µg/m³ 24-Hour CAAQS
	8.8	µg/m³ Annual CAAQS
Silica	5	µg/m³ AAQC
NO ₂	400	µg/m³ 1-Hour AAQC
	200	µg/m³ 24-Hour AAQC

Background Concentrations
 (90th Percentile, all except O₃)
 (O₃ 99th percentile)

TSP	44	µg/m³ (24-hour)
	22	µg/m³ (Annual)
PM ₁₀	24	µg/m³ (24-hour)
PM _{2.5}	13	µg/m³ (24-hour)
	6.6	µg/m³ (Annual)
Silica	1.5	µg/m³ (24-hour)
NO ₂	25	µg/m³ (1-hour)
	21	µg/m³ (24-hour)
O ₃	124	µg/m³ (1-hour)

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Relevant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Relevant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R01	Residence	638425	4750114	TSP	24	115	96%	0	0.0%	159	132%	2	0.1%
					Annual	7	11%	0	0.0%	29	48%	0	0.0%
				PM10	24	12	24%	0	0.0%	36	72%	0	0.0%
					Annual	1	6%	0	0.0%	19	69%	0	0.0%
				PM2.5	24	6	21%	0	0.0%	7	81%	0	0.0%
					Annual	1	6%	0	0.0%	3.3	66%	0	0.0%
R02	Church	638360	4750110	TSP	24	127	106%	1	0.1%	171	143%	2	0.1%
					Annual	6	10%	0	0.0%	28	46%	0	0.0%
				PM10	24	10	20%	0	0.0%	34	68%	0	0.0%
					Annual	0	5%	0	0.0%	19	71%	0	0.0%
				PM2.5	24	6	23%	0	0.0%	7	80%	0	0.0%
					Annual	0	5%	0	0.0%	3.5	70%	0	0.0%
Silica	24	2	40%	0	0.0%	337	84%	0	0.0%				
	Annual	0	5%	0	0.0%	73	36%	0	0.0%				
R03	Residence	638256	4750109	TSP	24	128	106%	1	0.1%	172	143%	1	0.1%
					Annual	5	8%	0	0.0%	27	44%	0	0.0%
				PM10	24	8	16%	0	0.0%	32	64%	0	0.0%
					Annual	0	4%	0	0.0%	19	71%	0	0.0%
				PM2.5	24	6	23%	0	0.0%	7	79%	0	0.0%
					Annual	0	4%	0	0.0%	3.5	70%	0	0.0%
Silica	24	2	40%	0	0.0%	359	90%	0	0.0%				
	Annual	0	4%	0	0.0%	74	37%	0	0.0%				

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R04	Residence	638287	4750108	TSP	24	130	108%	1	0.1%	174	145%	1	0.1%
					Annual	5	8%	0	0.0%	27	45%	0	0.0%
				PM10	24	9	17%	0	0.0%	33	65%	0	0.0%
					PM2.5	24	6	23%	0	0.0%	19	71%	0
				Annual		0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	41%	0	0.0%	3.6	71%	0	0.0%
				NO2	1	331	83%	0	0.0%	356	89%	0	0.0%
					24	54	27%	0	0.0%	75	37%	0	0.0%
R05	Residence	638228	4750108	TSP	24	125	104%	1	0.1%	169	141%	1	0.1%
					Annual	4	7%	0	0.0%	26	44%	0	0.0%
				PM10	24	8	16%	0	0.0%	32	64%	0	0.0%
				PM2.5	24	6	22%	0	0.0%	19	71%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	40%	0	0.0%	3.5	70%	0	0.0%
				NO2	1	333	83%	0	0.0%	358	89%	0	0.0%
					24	53	26%	0	0.0%	74	37%	0	0.0%
R06	Residence	638203	4750110	TSP	24	121	101%	1	0.1%	165	138%	1	0.1%
					Annual	4	7%	0	0.0%	26	44%	0	0.0%
				PM10	24	7	15%	0	0.0%	31	63%	0	0.0%
				PM2.5	24	6	22%	0	0.0%	19	70%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	39%	0	0.0%	3.4	69%	0	0.0%
				NO2	1	329	82%	0	0.0%	354	88%	0	0.0%
					24	52	26%	0	0.0%	73	36%	0	0.0%
R07	Residence	638139	4750102	TSP	24	110	92%	0	0.0%	154	128%	1	0.1%
					Annual	4	6%	0	0.0%	26	43%	0	0.0%
				PM10	24	7	14%	0	0.0%	31	62%	0	0.0%
				PM2.5	24	5	20%	0	0.0%	18	68%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	35%	0	0.0%	3.2	65%	0	0.0%
				NO2	1	305	76%	0	0.0%	330	83%	0	0.0%
					24	47	24%	0	0.0%	68	34%	0	0.0%
R08	Residence	638104	4750105	TSP	24	103	86%	0	0.0%	147	123%	1	0.1%
					Annual	4	6%	0	0.0%	26	43%	0	0.0%
				PM10	24	7	13%	0	0.0%	31	61%	0	0.0%
				PM2.5	24	5	19%	0	0.0%	18	67%	0	0.0%
					Annual	0	3%	0	0.0%	7	78%	0	0.0%
				Silica	24	2	33%	0	0.0%	3.1	63%	0	0.0%
				NO2	1	293	73%	0	0.0%	318	79%	0	0.0%
					24	45	22%	0	0.0%	66	33%	0	0.0%

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R09	Residence	637990	4750082	TSP	24	76	63%	0	0.0%	120	100%	0	0.00%
					Annual	3	5%	0	0.0%	25	42%	0	0.0%
				PM10	24	6	12%	0	0.0%	30	60%	0	0.00%
					Annual	4	14%	0	0.0%	17	62%	0	0.0%
				PM2.5	24	4	14%	0	0.0%	7	78%	0	0.0%
					Annual	0	3%	0	0.0%	2.7	54%	0	0.0%
				Silica	24	1	24%	0	0.0%	322	80%	0	0.0%
					1	297	74%	0	0.0%	54	27%	0	0.0%
R10	Residence	637952	4750077	TSP	24	67	56%	0	0.0%	111	93%	0	0.0%
					Annual	3	5%	0	0.0%	25	41%	0	0.0%
				PM10	24	6	12%	0	0.0%	30	60%	0	0.0%
					Annual	3	12%	0	0.0%	16	60%	0	0.0%
				PM2.5	24	3	12%	0	0.0%	7	78%	0	0.0%
					Annual	0	3%	0	0.0%	2.6	51%	0	0.0%
				Silica	24	1	21%	0	0.0%	324	81%	0	0.0%
					1	299	75%	0	0.0%	51	25%	0	0.0%
R11	Church	637441	4750189	TSP	24	41	34%	0	0.0%	85	71%	0	0.0%
					Annual	2	3%	0	0.0%	24	39%	0	0.0%
				PM10	24	5	11%	0	0.0%	29	59%	0	0.0%
					Annual	2	7%	0	0.0%	15	56%	0	0.0%
				PM2.5	24	2	7%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.1	42%	0	0.0%
				Silica	24	1	12%	0	0.0%	252	63%	0	0.0%
					1	227	57%	0	0.0%	39	20%	0	0.0%
R12	Residence	637471	4750310	TSP	24	47	39%	0	0.0%	91	76%	0	0.0%
					Annual	2	3%	0	0.0%	24	40%	0	0.0%
				PM10	24	5	11%	0	0.0%	29	59%	0	0.0%
					Annual	3	10%	0	0.0%	16	58%	0	0.0%
				PM2.5	24	3	10%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.2	45%	0	0.0%
				Silica	24	1	15%	0	0.0%	221	55%	0	0.0%
					1	196	49%	0	0.0%	40	20%	0	0.0%
R13	Residence	637452	4750415	TSP	24	53	44%	0	0.0%	97	81%	0	0.0%
					Annual	2	3%	0	0.0%	24	39%	0	0.0%
				PM10	24	6	11%	0	0.0%	30	59%	0	0.0%
					Annual	3	10%	0	0.0%	16	59%	0	0.0%
				PM2.5	24	3	10%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.3	47%	0	0.0%
				Silica	24	1	17%	0	0.0%	219	55%	0	0.0%
					1	194	48%	0	0.0%	42	21%	0	0.0%
				24	21	11%	0	0.0%					

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R14	Residence	637457	4750591	TSP	24	54	45%	0	0.0%	98	82%	0	0.0%
					Annual	2	3%	0	0.0%	24	39%	0	0.0%
				PM10	24	9	19%	0	0.0%	33	67%	0	0.0%
					PM2.5	24	3	10%	0	0.0%	16	58%	0
				Annual		0	2%	0	0.0%	7	77%	0	0.0%
				Silica	24	1	17%	0	0.0%	2.4	47%	0	0.0%
				NO2	1	167	42%	0	0.0%	192	48%	0	0.0%
					24	21	11%	0	0.0%	42	21%	0	0.0%
R15	Residence	637437	4750858	TSP	24	44	37%	0	0.0%	88	74%	0	0.0%
					Annual	1	2%	0	0.0%	23	39%	0	0.0%
				PM10	24	10	21%	0	0.0%	34	69%	0	0.0%
				PM2.5	24	2	8%	0	0.0%	15	57%	0	0.0%
					Annual	0	1%	0	0.0%	7	76%	0	0.0%
				Silica	24	1	14%	0	0.0%	2.2	44%	0	0.0%
				NO2	1	128	32%	0	0.0%	153	38%	0	0.0%
					24	16	8%	0	0.0%	37	18%	0	0.0%
R16	Residence	638112	4751073	TSP	24	84	70%	0	0.0%	128	107%	1	0.1%
					Annual	3	4%	0	0.0%	25	41%	0	0.0%
				PM10	24	18	36%	0	0.0%	42	84%	0	0.0%
				PM2.5	24	4	15%	0	0.0%	17	63%	0	0.0%
					Annual	0	2%	0	0.0%	7	77%	0	0.0%
				Silica	24	1	29%	0	0.0%	3.0	59%	0	0.0%
				NO2	1	347	87%	0	0.0%	372	93%	0	0.0%
					24	36	18%	0	0.0%	57	28%	0	0.0%
R17	Residence	638288	4751083	TSP	24	90	75%	0	0.0%	134	112%	1	0.1%
					Annual	3	6%	0	0.0%	25	42%	0	0.0%
				PM10	24	16	31%	0	0.0%	40	79%	0	0.0%
				PM2.5	24	4	16%	0	0.0%	17	65%	0	0.0%
					Annual	0	3%	0	0.0%	7	78%	0	0.0%
				Silica	24	1	29%	0	0.0%	3.0	59%	0	0.0%
				NO2	1	260	65%	0	0.0%	285	71%	0	0.0%
					24	30	15%	0	0.0%	51	25%	0	0.0%

Notes:

Values in bold indicate excursions above the relevant criteria

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R04	Residence	638287	4750108	TSP	24	130	109%	1	0.1%	174	145%	1	0.1%
					Annual	6	10%	0	0.0%	28	46%	0	0.0%
				PM10	24	21	41%	0	0.0%	45	89%	0	0.0%
					PM2.5	24	6	23%	0	0.0%	19	71%	0
				Annual		0	5%	0	0.0%	7	80%	0	0.0%
				Silica	24	2	41%	0	0.0%	3.6	71%	0	0.0%
				NO2	1	331	83%	0	0.0%	356	89%	0	0.0%
					24	54	27%	0	0.0%	75	37%	0	0.0%
R05	Residence	638228	4750108	TSP	24	125	104%	1	0.1%	169	141%	1	0.1%
					Annual	5	9%	0	0.0%	27	45%	0	0.0%
				PM10	24	13	27%	0	0.0%	37	75%	0	0.0%
				PM2.5	24	6	22%	0	0.0%	19	71%	0	0.0%
					Annual	0	5%	0	0.0%	7	80%	0	0.0%
				Silica	24	2	40%	0	0.0%	3.5	70%	0	0.0%
				NO2	1	333	83%	0	0.0%	358	89%	0	0.0%
					24	53	26%	0	0.0%	74	37%	0	0.0%
R06	Residence	638203	4750110	TSP	24	122	102%	1	0.1%	166	138%	1	0.1%
					Annual	5	8%	0	0.0%	27	45%	0	0.0%
				PM10	24	14	29%	0	0.0%	38	77%	0	0.0%
				PM2.5	24	6	22%	0	0.0%	19	70%	0	0.0%
					Annual	0	5%	0	0.0%	7	80%	0	0.0%
				Silica	24	2	39%	0	0.0%	3.4	69%	0	0.0%
				NO2	1	329	82%	0	0.0%	354	88%	0	0.0%
					24	52	26%	0	0.0%	73	36%	0	0.0%
R07	Residence	638139	4750102	TSP	24	110	92%	0	0.0%	154	129%	1	0.1%
					Annual	4	7%	0	0.0%	26	44%	0	0.0%
				PM10	24	9	17%	0	0.0%	33	65%	0	0.0%
				PM2.5	24	5	20%	0	0.0%	18	68%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	35%	0	0.0%	3.3	65%	0	0.0%
				NO2	1	305	76%	0	0.0%	330	83%	0	0.0%
					24	47	24%	0	0.0%	68	34%	0	0.0%
R08	Residence	638104	4750105	TSP	24	104	86%	0	0.0%	148	123%	1	0.1%
					Annual	4	7%	0	0.0%	26	43%	0	0.0%
				PM10	24	8	16%	0	0.0%	32	64%	0	0.0%
				PM2.5	24	5	19%	0	0.0%	18	67%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	33%	0	0.0%	3.1	63%	0	0.0%
				NO2	1	293	73%	0	0.0%	318	79%	0	0.0%
					24	45	22%	0	0.0%	66	33%	0	0.0%

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R09	Residence	637990	4750082	TSP	24	76	63%	0	0.0%	120	100%	0	0.00%
					Annual	3	5%	0	0.0%	25	42%	0	0.0%
				PM10	24	6	12%	0	0.0%	30	60%	0	0.00%
					Annual	4	14%	0	0.0%	17	62%	0	0.0%
				PM2.5	24	4	14%	0	0.0%	7	78%	0	0.0%
					Annual	0	3%	0	0.0%	2.7	54%	0	0.0%
				Silica	24	1	24%	0	0.0%	322	80%	0	0.0%
NO2	1	297	74%		0	0.0%	54	27%	0	0.0%			
	24	33	17%	0	0.0%	112	93%	0	0.0%				
R10	Residence	637952	4750077	TSP	24	68	56%	0	0.0%	25	42%	0	0.0%
					Annual	3	5%	0	0.0%	31	61%	0	0.0%
				PM10	24	7	13%	0	0.0%	16	61%	0	0.0%
					Annual	24	3	12%	0	0.0%	7	78%	0
				PM2.5	24	3	12%	0	0.0%	2.6	51%	0	0.0%
					Annual	0	3%	0	0.0%	324	81%	0	0.0%
				Silica	24	1	21%	0	0.0%	51	25%	0	0.0%
NO2	1	299	75%		0	0.0%	93	77%	0	0.0%			
	24	30	15%	0	0.0%	24	40%	0	0.0%				
R11	Church	637441	4750189	TSP	24	49	41%	0	0.0%	37	73%	0	0.0%
					Annual	2	3%	0	0.0%	15	56%	0	0.0%
				PM10	24	13	25%	0	0.0%	7	77%	0	0.0%
					Annual	24	2	8%	0	0.0%	2.6	52%	0
				PM2.5	24	2	8%	0	0.0%	252	63%	0	0.0%
					Annual	0	2%	0	0.0%	39	20%	0	0.0%
				Silica	24	1	22%	0	0.0%	90	75%	0	0.0%
NO2	1	227	57%		0	0.0%	24	40%	0	0.0%			
	24	18	9%	0	0.0%	33	65%	0	0.0%				
R12	Residence	637471	4750310	TSP	24	46	39%	0	0.0%	16	58%	0	0.0%
					Annual	2	3%	0	0.0%	7	77%	0	0.0%
				PM10	24	9	17%	0	0.0%	2.3	45%	0	0.0%
					Annual	24	3	10%	0	0.0%	221	55%	0
				PM2.5	24	3	10%	0	0.0%	40	20%	0	0.0%
					Annual	0	2%	0	0.0%	99	82%	0	0.0%
				Silica	24	1	15%	0	0.0%	24	40%	0	0.0%
NO2	1	196	49%		0	0.0%	34	69%	0	0.0%			
	24	19	9%	0	0.0%	16	59%	0	0.0%				
R13	Residence	637452	4750415	TSP	24	55	46%	0	0.0%	7	77%	0	0.0%
					Annual	2	3%	0	0.0%	2.4	47%	0	0.0%
				PM10	24	10	21%	0	0.0%	219	55%	0	0.0%
					Annual	24	3	11%	0	0.0%	44	22%	0
				PM2.5	24	3	11%	0	0.0%				
					Annual	0	2%	0	0.0%				
				Silica	24	1	17%	0	0.0%				
NO2	1	194	48%		0	0.0%							
	24	23	11%	0	0.0%								

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R14	Residence	637457	4750591	TSP	24	63	52%	0	0.0%	107	89%	0	0.0%
					Annual	2	3%	0	0.0%	24	40%	0	0.0%
				PM10	24	13	27%	0	0.0%	37	75%	0	0.0%
					PM2.5	24	3	12%	0	0.0%	16	60%	0
				Annual		0	2%	0	0.0%	7	77%	0	0.0%
				Silica	24	1	20%	0	0.0%	2.5	50%	0	0.0%
				NO2	1	167	42%	0	0.0%	192	48%	0	0.0%
					24	26	13%	0	0.0%	47	24%	0	0.0%
R15	Residence	637437	4750858	TSP	24	65	54%	0	0.0%	109	91%	0	0.0%
					Annual	1	2%	0	0.0%	23	39%	0	0.0%
				PM10	24	15	30%	0	0.0%	39	78%	0	0.0%
				PM2.5	24	3	12%	0	0.0%	16	61%	0	0.0%
					Annual	0	1%	0	0.0%	7	76%	0	0.0%
				Silica	24	1	23%	0	0.0%	2.6	53%	0	0.0%
				NO2	1	164	41%	0	0.0%	189	47%	0	0.0%
					24	26	13%	0	0.0%	47	24%	0	0.0%
R16	Residence	638112	4751073	TSP	24	57	48%	0	0.0%	101	84%	0	0.0%
					Annual	2	4%	0	0.0%	24	40%	0	0.0%
				PM10	24	7	14%	0	0.0%	31	62%	0	0.0%
				PM2.5	24	3	9%	0	0.0%	16	58%	0	0.0%
					Annual	0	2%	0	0.0%	7	77%	0	0.0%
				Silica	24	1	18%	0	0.0%	2.4	48%	0	0.0%
				NO2	1	188	47%	0	0.0%	213	53%	0	0.0%
					24	20	10%	0	0.0%	41	21%	0	0.0%
R17	Residence	638288	4751083	TSP	24	67	56%	0	0.0%	111	93%	0	0.0%
					Annual	2	4%	0	0.0%	24	41%	0	0.0%
				PM10	24	9	19%	0	0.0%	33	67%	0	0.0%
				PM2.5	24	3	11%	0	0.0%	16	60%	0	0.0%
					Annual	0	2%	0	0.0%	7	77%	0	0.0%
				Silica	24	1	22%	0	0.0%	2.6	52%	0	0.0%
				NO2	1	231	58%	0	0.0%	256	64%	0	0.0%
					24	22	11%	0	0.0%	43	22%	0	0.0%

Notes:

Values in bold indicate excursions above the relevant criteria

Table 4: Cumulative Effects Assessment - Operations in Phase 2
 Modelled Values & Frequency of Excursions above the Relevant Criteria

RWDI# 2202166

Days of Valid Meteorological Data 1745

Relevant Criteria:	TSP	120	µg/m³ 24-Hour AAQC
		60	µg/m³ Annual AAQC
	PM ₁₀	50	µg/m³ Interim AAQC
	PM _{2.5}	27	µg/m³ 24-Hour CAAQS
		8.8	µg/m³ Annual CAAQS
	Silica	5	µg/m³ AAQC
	NO ₂	400	µg/m³ 1-Hour AAQC
		200	µg/m³ 24-Hour AAQC

Background Concentrations (90th Percentile, all except O ₃) (O ₃ 99th percentile)	TSP	44	µg/m³ (24-hour)
		22	µg/m³ (Annual)
	PM ₁₀	24	µg/m³ (24-hour)
	PM _{2.5}	13	µg/m³ (24-hour)
		6.6	µg/m³ (Annual)
	Silica	1.5	µg/m³ (24-hour)
	NO ₂	25	µg/m³ (1-hour)
		21	µg/m³ (24-hour)
O ₃	124	µg/m³ (1-hour)	

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Relevant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Relevant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R01	Residence	638425	4750114	TSP	24	115	96%	0	0.0%	159	132%	2	0.1%
					Annual	7	12%	0	0.0%	29	49%	0	0.0%
				PM10	24	12	23%	0	0.0%	36	71%	0	0.0%
					Annual	1	6%	0	0.0%	19	69%	0	0.0%
				PM2.5	24	6	21%	0	0.0%	7	81%	0	0.0%
					Annual	1	6%	0	0.0%	3.3	66%	0	0.0%
				Silica	24	2	36%	0	0.0%	344	86%	0	0.0%
					NO2	1	319	80%	0	0.0%	68	34%	0
R02	Church	638360	4750110	TSP	24	127	106%	1	0.1%	171	143%	2	0.1%
					Annual	6	10%	0	0.0%	28	47%	0	0.0%
				PM10	24	10	20%	0	0.0%	34	68%	0	0.0%
					Annual	0	5%	0	0.0%	19	71%	0	0.0%
				PM2.5	24	6	23%	0	0.0%	7	80%	0	0.0%
					Annual	0	5%	0	0.0%	3.5	70%	0	0.0%
				Silica	24	2	40%	0	0.0%	337	84%	0	0.0%
					NO2	1	312	78%	0	0.0%	73	36%	0
R03	Residence	638256	4750109	TSP	24	128	107%	1	0.1%	172	143%	1	0.1%
					Annual	5	9%	0	0.0%	27	45%	0	0.0%
				PM10	24	8	16%	0	0.0%	32	64%	0	0.0%
					Annual	0	5%	0	0.0%	19	71%	0	0.0%
				PM2.5	24	6	23%	0	0.0%	7	80%	0	0.0%
					Annual	0	5%	0	0.0%	3.5	70%	0	0.0%
				Silica	24	2	40%	0	0.0%	359	90%	0	0.0%
					NO2	1	334	83%	0	0.0%	74	37%	0
	24	53	27%	0	0.0%								

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R04	Residence	638287	4750108	TSP	24	130	108%	1	0.1%	174	145%	2	0.1%
					Annual	5	9%	0	0.0%	27	46%	0	0.0%
				PM10	24	8	17%	0	0.0%	32	65%	0	0.0%
					PM2.5	24	6	23%	0	0.0%	19	71%	0
				Annual		0	5%	0	0.0%	7	80%	0	0.0%
				Silica	24	2	41%	0	0.0%	3.6	71%	0	0.0%
				NO2	1	331	83%	0	0.0%	356	89%	0	0.0%
					24	54	27%	0	0.0%	75	37%	0	0.0%
R05	Residence	638228	4750108	TSP	24	125	104%	1	0.1%	169	141%	1	0.1%
					Annual	5	8%	0	0.0%	27	45%	0	0.0%
				PM10	24	7	15%	0	0.0%	31	63%	0	0.0%
				PM2.5	24	6	22%	0	0.0%	19	71%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	40%	0	0.0%	3.5	70%	0	0.0%
				NO2	1	333	83%	0	0.0%	358	89%	0	0.0%
					24	53	26%	0	0.0%	74	37%	0	0.0%
R06	Residence	638203	4750110	TSP	24	121	101%	1	0.1%	165	138%	1	0.1%
					Annual	5	8%	0	0.0%	27	45%	0	0.0%
				PM10	24	7	14%	0	0.0%	31	62%	0	0.0%
				PM2.5	24	6	22%	0	0.0%	19	70%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	39%	0	0.0%	3.4	69%	0	0.0%
				NO2	1	329	82%	0	0.0%	354	88%	0	0.0%
					24	52	26%	0	0.0%	73	36%	0	0.0%
R07	Residence	638139	4750102	TSP	24	110	92%	0	0.0%	154	128%	1	0.1%
					Annual	4	7%	0	0.0%	26	44%	0	0.0%
				PM10	24	6	13%	0	0.0%	30	61%	0	0.0%
				PM2.5	24	5	20%	0	0.0%	18	68%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	35%	0	0.0%	3.2	65%	0	0.0%
				NO2	1	305	76%	0	0.0%	330	83%	0	0.0%
					24	47	24%	0	0.0%	68	34%	0	0.0%
R08	Residence	638104	4750105	TSP	24	103	86%	0	0.0%	147	123%	1	0.1%
					Annual	4	7%	0	0.0%	26	43%	0	0.0%
				PM10	24	6	12%	0	0.0%	30	60%	0	0.0%
				PM2.5	24	5	19%	0	0.0%	18	67%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	33%	0	0.0%	3.1	63%	0	0.0%
				NO2	1	293	73%	0	0.0%	318	79%	0	0.0%
					24	45	22%	0	0.0%	66	33%	0	0.0%

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R09	Residence	637990	4750082	TSP	24	76	63%	0	0.0%	120	100%	0	0.00%
					Annual	3	6%	0	0.0%	25	42%	0	0.0%
				PM10	24	9	17%	0	0.0%	33	65%	0	0.00%
					Annual	4	14%	0	0.0%	17	62%	0	0.0%
				PM2.5	24	4	14%	0	0.0%	7	78%	0	0.0%
					Annual	0	3%	0	0.0%	2.7	54%	0	0.0%
				Silica	24	1	24%	0	0.0%	322	80%	0	0.0%
					1	297	74%	0	0.0%	54	27%	0	0.0%
R10	Residence	637952	4750077	TSP	24	68	56%	0	0.0%	112	93%	0	0.0%
					Annual	3	5%	0	0.0%	25	42%	0	0.0%
				PM10	24	12	24%	0	0.0%	36	72%	0	0.0%
					Annual	3	12%	0	0.0%	16	60%	0	0.0%
				PM2.5	24	3	12%	0	0.0%	7	78%	0	0.0%
					Annual	0	3%	0	0.0%	2.6	51%	0	0.0%
				Silica	24	1	21%	0	0.0%	324	81%	0	0.0%
					1	299	75%	0	0.0%	51	25%	0	0.0%
R11	Church	637441	4750189	TSP	24	41	34%	0	0.0%	85	71%	0	0.0%
					Annual	2	3%	0	0.0%	24	40%	0	0.0%
				PM10	24	6	12%	0	0.0%	30	60%	0	0.0%
					Annual	2	7%	0	0.0%	15	56%	0	0.0%
				PM2.5	24	2	7%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.1	42%	0	0.0%
				Silica	24	1	12%	0	0.0%	252	63%	0	0.0%
					1	227	57%	0	0.0%	39	20%	0	0.0%
R12	Residence	637471	4750310	TSP	24	47	39%	0	0.0%	91	76%	0	0.0%
					Annual	2	3%	0	0.0%	24	40%	0	0.0%
				PM10	24	9	19%	0	0.0%	33	67%	0	0.0%
					Annual	3	10%	0	0.0%	16	58%	0	0.0%
				PM2.5	24	3	10%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.2	45%	0	0.0%
				Silica	24	1	15%	0	0.0%	221	55%	0	0.0%
					1	196	49%	0	0.0%	40	20%	0	0.0%
R13	Residence	637452	4750415	TSP	24	53	44%	0	0.0%	97	81%	0	0.0%
					Annual	2	4%	0	0.0%	24	40%	0	0.0%
				PM10	24	11	22%	0	0.0%	35	70%	0	0.0%
					Annual	3	10%	0	0.0%	16	59%	0	0.0%
				PM2.5	24	3	10%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.3	47%	0	0.0%
				Silica	24	1	17%	0	0.0%	219	55%	0	0.0%
					1	194	49%	0	0.0%	42	21%	0	0.0%
				24	21	11%	0	0.0%					

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R14	Residence	637457	4750591	TSP	24	62	51%	0	0.0%	106	88%	0	0.0%
					Annual	3	5%	0	0.0%	25	41%	0	0.0%
				PM10	24	17	34%	0	0.0%	41	82%	0	0.0%
					PM2.5	24	3	11%	0	0.0%	16	59%	0
				Annual		0	3%	0	0.0%	7	78%	0	0.0%
				Silica	24	1	21%	0	0.0%	2.5	51%	0	0.0%
				NO2	1	220	55%	0	0.0%	245	61%	0	0.0%
					24	27	14%	0	0.0%	48	24%	0	0.0%
R15	Residence	637437	4750858	TSP	24	91	76%	0	0.0%	135	113%	1	0.1%
					Annual	2	3%	0	0.0%	24	40%	0	0.0%
				PM10	24	24	47%	0	0.0%	48	95%	0	0.0%
					PM2.5	24	4	16%	0	0.0%	17	65%	0
				Annual		0	2%	0	0.0%	7	77%	0	0.0%
				Silica	24	2	36%	0	0.0%	3.3	66%	0	0.0%
				NO2	1	236	59%	0	0.0%	261	65%	0	0.0%
					24	37	18%	0	0.0%	58	29%	0	0.0%
R16	Residence	638112	4751073	TSP	24	68	56%	0	0.0%	112	93%	0	0.0%
					Annual	3	5%	0	0.0%	25	41%	0	0.0%
				PM10	24	12	23%	0	0.0%	36	71%	0	0.0%
					PM2.5	24	3	12%	0	0.0%	16	60%	0
				Annual		0	2%	0	0.0%	7	77%	0	0.0%
				Silica	24	1	20%	0	0.0%	2.5	50%	0	0.0%
				NO2	1	188	47%	0	0.0%	213	53%	0	0.0%
					24	32	16%	0	0.0%	53	27%	0	0.0%
R17	Residence	638288	4751083	TSP	24	68	56%	0	0.0%	112	93%	0	0.0%
					Annual	3	5%	0	0.0%	25	41%	0	0.0%
				PM10	24	10	19%	0	0.0%	34	67%	0	0.0%
					PM2.5	24	3	12%	0	0.0%	16	60%	0
				Annual		0	2%	0	0.0%	7	77%	0	0.0%
				Silica	24	1	22%	0	0.0%	2.6	52%	0	0.0%
				NO2	1	232	58%	0	0.0%	257	64%	0	0.0%
					24	24	12%	0	0.0%	45	23%	0	0.0%

Notes:

Values in bold indicate excursions above the relevant criteria

Table 5: Cumulative Effects Assessment - Operations in Phases 3 and 4
 Modelled Values & Frequency of Excursions above the Relevant Criteria

RWDI# 2202166

Days of Valid Meteorological Data 1745

Relevant Criteria:	TSP	120	µg/m³ 24-Hour AAQC
		60	µg/m³ Annual AAQC
	PM ₁₀	50	µg/m³ Interim AAQC
	PM _{2.5}	27	µg/m³ 24-Hour CAAQS
		8.8	µg/m³ Annual CAAQS
	Silica	5	µg/m³ AAQC
	NO ₂	400	µg/m³ 1-Hour AAQC
		200	µg/m³ 24-Hour AAQC

Background Concentrations (90th Percentile, all except O ₃) (O ₃ 99th percentile)	TSP	44	µg/m³ (24-hour)
		22	µg/m³ (Annual)
	PM ₁₀	24	µg/m³ (24-hour)
	PM _{2.5}	13	µg/m³ (24-hour)
		6.6	µg/m³ (Annual)
	Silica	1.5	µg/m³ (24-hour)
	NO ₂	25	µg/m³ (1-hour)
		21	µg/m³ (24-hour)
O ₃	124	µg/m³ (1-hour)	

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Relevant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Relevant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R01	Residence	638425	4750114	TSP	24	115	96%	0	0.0%	159	132%	2	0.1%
					Annual	7	12%	0	0.0%	29	49%	0	0.0%
				PM10	24	12	23%	0	0.0%	36	71%	0	0.0%
					Annual	1	6%	0	0.0%	19	69%	0	0.0%
				PM2.5	24	6	21%	0	0.0%	7	81%	0	0.0%
					Annual	1	6%	0	0.0%	3.3	66%	0	0.0%
				Silica	24	2	36%	0	0.0%	344	86%	0	0.0%
					NO2	1	319	80%	0	0.0%	68	34%	0
R02	Church	638360	4750110	TSP	24	127	106%	1	0.1%	171	143%	2	0.1%
					Annual	6	11%	0	0.0%	28	47%	0	0.0%
				PM10	24	10	20%	0	0.0%	34	68%	0	0.0%
					Annual	0	6%	0	0.0%	19	71%	0	0.0%
				PM2.5	24	6	23%	0	0.0%	7	81%	0	0.0%
					Annual	0	6%	0	0.0%	3.5	70%	0	0.0%
				Silica	24	2	40%	0	0.0%	337	84%	0	0.0%
					NO2	1	312	78%	0	0.0%	73	36%	0
R03	Residence	638256	4750109	TSP	24	128	107%	1	0.1%	172	143%	1	0.1%
					Annual	5	9%	0	0.0%	27	46%	0	0.0%
				PM10	24	8	16%	0	0.0%	32	64%	0	0.0%
					Annual	0	5%	0	0.0%	19	71%	0	0.0%
				PM2.5	24	6	23%	0	0.0%	7	80%	0	0.0%
					Annual	0	5%	0	0.0%	3.5	70%	0	0.0%
				Silica	24	2	40%	0	0.0%	359	90%	0	0.0%
					NO2	1	334	83%	0	0.0%	74	37%	0
	24	53	27%	0	0.0%								

Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R04	Residence	638287	4750108	TSP	24	130	108%	1	0.1%	174	145%	2	0.1%
					Annual	6	9%	0	0.0%	28	46%	0	0.0%
				PM10	24	8	17%	0	0.0%	32	65%	0	0.0%
					PM2.5	24	6	23%	0	0.0%	19	71%	0
				Annual		0	5%	0	0.0%	7	80%	0	0.0%
				Silica	24	2	41%	0	0.0%	3.6	71%	0	0.0%
				NO2	1	331	83%	0	0.0%	356	89%	0	0.0%
					24	54	27%	0	0.0%	75	37%	0	0.0%
R05	Residence	638228	4750108	TSP	24	125	104%	1	0.1%	169	141%	1	0.1%
					Annual	5	9%	0	0.0%	27	45%	0	0.0%
				PM10	24	9	18%	0	0.0%	33	66%	0	0.0%
				PM2.5	24	6	22%	0	0.0%	19	71%	0	0.0%
					Annual	0	5%	0	0.0%	7	80%	0	0.0%
				Silica	24	2	40%	0	0.0%	3.5	70%	0	0.0%
				NO2	1	333	83%	0	0.0%	358	89%	0	0.0%
					24	53	26%	0	0.0%	74	37%	0	0.0%
R06	Residence	638203	4750110	TSP	24	122	101%	1	0.1%	166	138%	1	0.1%
					Annual	5	8%	0	0.0%	27	45%	0	0.0%
				PM10	24	10	19%	0	0.0%	34	67%	0	0.0%
				PM2.5	24	6	22%	0	0.0%	19	70%	0	0.0%
					Annual	0	5%	0	0.0%	7	80%	0	0.0%
				Silica	24	2	38%	0	0.0%	3.4	68%	0	0.0%
				NO2	1	329	82%	0	0.0%	354	88%	0	0.0%
					24	52	26%	0	0.0%	73	36%	0	0.0%
R07	Residence	638139	4750102	TSP	24	110	92%	0	0.0%	154	128%	1	0.1%
					Annual	5	8%	0	0.0%	27	44%	0	0.0%
				PM10	24	10	20%	0	0.0%	34	68%	0	0.0%
				PM2.5	24	5	20%	0	0.0%	18	68%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	35%	0	0.0%	3.2	65%	0	0.0%
				NO2	1	305	76%	0	0.0%	330	83%	0	0.0%
					24	47	24%	0	0.0%	68	34%	0	0.0%
R08	Residence	638104	4750105	TSP	24	103	86%	0	0.0%	147	123%	1	0.1%
					Annual	4	7%	0	0.0%	26	44%	0	0.0%
				PM10	24	8	17%	0	0.0%	32	65%	0	0.0%
				PM2.5	24	5	19%	0	0.0%	18	67%	0	0.0%
					Annual	0	4%	0	0.0%	7	79%	0	0.0%
				Silica	24	2	33%	0	0.0%	3.1	63%	0	0.0%
				NO2	1	293	73%	0	0.0%	318	79%	0	0.0%
					24	45	22%	0	0.0%	66	33%	0	0.0%


Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R09	Residence	637990	4750082	TSP	24	76	63%	0	0.0%	120	100%	0	0.00%
					Annual	4	6%	0	0.0%	26	43%	0	0.0%
				PM10	24	9	18%	0	0.0%	33	66%	0	0.00%
					Annual	4	14%	0	0.0%	17	62%	0	0.0%
				PM2.5	24	4	14%	0	0.0%	7	79%	0	0.0%
					Annual	0	4%	0	0.0%	2.7	54%	0	0.0%
				Silica	24	1	24%	0	0.0%	322	80%	0	0.0%
					1	297	74%	0	0.0%	54	27%	0	0.0%
R10	Residence	637952	4750077	TSP	24	68	56%	0	0.0%	112	93%	0	0.0%
					Annual	4	6%	0	0.0%	26	43%	0	0.0%
				PM10	24	10	19%	0	0.0%	34	67%	0	0.0%
					Annual	3	12%	0	0.0%	16	61%	0	0.0%
				PM2.5	24	3	12%	0	0.0%	7	78%	0	0.0%
					Annual	0	3%	0	0.0%	2.6	51%	0	0.0%
				Silica	24	1	21%	0	0.0%	324	81%	0	0.0%
					1	299	75%	0	0.0%	51	25%	0	0.0%
R11	Church	637441	4750189	TSP	24	41	34%	0	0.0%	85	71%	0	0.0%
					Annual	2	3%	0	0.0%	24	40%	0	0.0%
				PM10	24	10	20%	0	0.0%	34	68%	0	0.0%
					Annual	2	7%	0	0.0%	15	56%	0	0.0%
				PM2.5	24	2	7%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.1	42%	0	0.0%
				Silica	24	1	12%	0	0.0%	252	63%	0	0.0%
					1	227	57%	0	0.0%	39	20%	0	0.0%
R12	Residence	637471	4750310	TSP	24	80	66%	0	0.0%	124	103%	1	0.1%
					Annual	3	4%	0	0.0%	25	41%	0	0.0%
				PM10	24	28	57%	0	0.0%	52	105%	1	0.1%
					Annual	3	11%	0	0.0%	16	59%	0	0.0%
				PM2.5	24	3	11%	0	0.0%	7	78%	0	0.0%
					Annual	0	3%	0	0.0%	3.7	73%	0	0.0%
				Silica	24	2	43%	0	0.0%	221	55%	0	0.0%
					1	196	49%	0	0.0%	46	23%	0	0.0%
R13	Residence	637452	4750415	TSP	24	71	59%	0	0.0%	115	96%	0	0.0%
					Annual	3	5%	0	0.0%	25	42%	0	0.0%
				PM10	24	25	49%	0	0.0%	49	97%	0	0.0%
					Annual	4	13%	0	0.0%	17	62%	0	0.0%
				PM2.5	24	4	13%	0	0.0%	7	78%	0	0.0%
					Annual	0	3%	0	0.0%	3.0	60%	0	0.0%
				Silica	24	1	30%	0	0.0%	219	55%	0	0.0%
					1	194	49%	0	0.0%	45	23%	0	0.0%
NO2	24	24	12%	0	0.0%								


Receptor		UTM Coordinates		Contaminant	Averaging Period	With No Background Concentration				With Additional Background Concentrations			
ID	Type	X	Y			Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria	Maximum Predicted 24-Hour Concentration	Percentage of Revelant Criteria	Number of Predicted Excursions Above Criteria over 5 Years	Frequency of Predicted Excursions Above Criteria
		(m)	(m)		(hours)	(µg/m³)	(%)		(%)	(µg/m³)	(%)		(%)
R14	Residence	637457	4750591	TSP	24	105	88%	0	0.0%	149	124%	2	0.1%
					Annual	3	5%	0	0.0%	25	42%	0	0.0%
				PM10	24	31	63%	0	0.0%	55	111%	0	0.0%
					Annual	0	2%	0	0.0%	18	67%	0	0.0%
				PM2.5	24	5	19%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	3.4	69%	0	0.0%
				Silica	24	2	39%	0	0.0%	280	70%	0	0.0%
					Annual	0	2%	0	0.0%	66	33%	0	0.0%
R15	Residence	637437	4750858	TSP	24	62	52%	0	0.0%	106	89%	0	0.0%
					Annual	2	3%	0	0.0%	24	40%	0	0.0%
				PM10	24	11	22%	0	0.0%	35	70%	0	0.0%
					Annual	0	2%	0	0.0%	16	58%	0	0.0%
				PM2.5	24	3	10%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.2	43%	0	0.0%
				Silica	24	1	13%	0	0.0%	249	62%	0	0.0%
					Annual	0	2%	0	0.0%	37	19%	0	0.0%
R16	Residence	638112	4751073	TSP	24	65	54%	0	0.0%	109	91%	0	0.0%
					Annual	3	4%	0	0.0%	25	41%	0	0.0%
				PM10	24	10	20%	0	0.0%	34	68%	0	0.0%
					Annual	0	2%	0	0.0%	16	60%	0	0.0%
				PM2.5	24	3	11%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.3	46%	0	0.0%
				Silica	24	1	16%	0	0.0%	213	53%	0	0.0%
					Annual	0	2%	0	0.0%	51	25%	0	0.0%
R17	Residence	638288	4751083	TSP	24	69	58%	0	0.0%	113	94%	0	0.0%
					Annual	3	5%	0	0.0%	25	41%	0	0.0%
				PM10	24	11	22%	0	0.0%	35	70%	0	0.0%
					Annual	0	2%	0	0.0%	16	60%	0	0.0%
				PM2.5	24	3	11%	0	0.0%	7	77%	0	0.0%
					Annual	0	2%	0	0.0%	2.4	48%	0	0.0%
				Silica	24	1	18%	0	0.0%	256	64%	0	0.0%
					Annual	0	2%	0	0.0%	47	23%	0	0.0%

Notes:

Values in bold indicate excursions above the relevant criteria

FIGURES





Phase Extraction, License Boundary, Additional Lands & Receptor Locations




Drawn by: LJN	Figure: 1
Approx. Scale: 1:12,000	
Date Revised: Jan 31, 2022	



Map Projection: NAD 1983 UTM Zone 17N
 Law Quarry - Port Colborne ON

Project #: 2202166

Map Document: C:\Users\LJN\OneDrive - ROWAN WILLIAMS DAVIES & IRWIN INC\Desktop\GIS\Law Quarry\Law Quarry.aprx



Location of Sources - Asphalt Plant


Map Projection: NAD 1983 UTM Zone 17N
 Law Quarry - Port Colborne ON



Drawn by: LJN	Figure: 2A
Approx. Scale: 1:1,500	
Date Revised: Jan 31, 2022	



Project #: 2202166



Location of Sources - Phase 1A


Map Projection: NAD 1983 UTM Zone 17N
Law Quarry - Port Colborne ON



Drawn by: LJN	Figure: 2B
Approx. Scale: 1:4,000	
Date Revised: Dec 21, 2021	



Project #: 2202166



Location of Sources - Phase 1B

Map Projection: NAD 1983 UTM Zone 17N
 Law Quarry - Port Colborne ON

True North



Drawn by: LJN Figure: 2C


Approx. Scale: 1:4,000

Date Revised: Dec 21, 2021

Project #: 2202166



Map Document: C:\Users\l\OneDrive - ROWAN WILLIAMS DAVIES & IRWIN INC\Desktop\GIS\Law Quarry\Law Quarry.aprx



Location of Sources - Phase 2

Map Projection: NAD 1983 UTM Zone 17N
Law Quarry - Port Colborne ON




Drawn by: LJN | Figure: 2D

Approx. Scale: 1:5,000

Date Revised: Dec 21, 2021

Project #: 2202166





Location of Sources - Phase 3



True North

Drawn by: LJN Figure: 2E

Approx. Scale: 1:5,000

Date Revised: Dec 21, 2021



Project #: 2202166



Reeb Limit of Extraction and Boundary of Licensed Area

Map Projection: NAD 1983 UTM Zone 17N
Law Quarry - Port Colborne ON



Drawn by: LJN | Figure: 3


Approx. Scale: 1:8,000

Date Revised: Jan 31, 2022

Project #: 2202166



APPENDIX A



Appendix A: Blasting Operations Emission Spreadsheet

Project #2202166

Law Crushed Stone

WESTERN SURFACE COAL MINING - AP-42 Section 11.9

Blasting operation particulate emissions: $E = 0.00022 k * A^{1.5}$

E emission factor
k particle size multiplier (1.13, 1.0, 0.52 and 0.03 for TSP, PM₃₀, PM₁₀ and PM_{2.5}, respectively)
A blast surface area (m²)

Source ID	Source Description	Total Blast Area (m ²)	Number of Blasts			Base AP-42 Emission Factor				Base Emission Rate				Additional Control Efficiency Applied (%)	Final Controlled Emission Rate							
			Hourly	Daily	Annual	TSP (kg/blast)	PM ₁₀ (kg/blast)	PM _{2.5} (kg/blast)	Silica (kg/blast)	TSP (g/s)	PM ₁₀ (g/s)	PM _{2.5} (g/s)	Silica (g/s)		TSP (g/s)	Data Quality Rating	PM ₁₀ (g/s)	Data Quality Rating	PM _{2.5} (g/s)	Data Quality Rating	Silica (g/s)	Data Quality Rating
Blasting at Law Crushed Stone																						
BLAST	Typical weekly blast	1000	1	1	25	7.0E+00	3.6E+00	2.1E-01	2.9E-01	1.9E+00	1.0E+00	5.8E-02	7.9E-02		1.9E+00	C	1.0E+00	C	5.8E-02	C	7.9E-02	C
Blasting at Reeb Quarry																						
REEB_BL	Typical weekly blast	1000	1	1	25	7.0E+00	3.6E+00	2.1E-01	2.9E-01	1.9E+00	1.0E+00	5.8E-02	7.9E-02		1.9E+00	C	1.0E+00	C	5.8E-02	C	7.9E-02	C

Sample calculation for uncontrolled TSP emission factor for Source BLAST: Typical weekly blast.


$$EF = 0.00022 \times (1) \times (1000 \text{ m})^{1.5} = 7.0E+00 \text{ kg TSP / blast}$$

Sample calculation for TSP emission rate for Source BLAST: Typical weekly blast.

1 blast	7.0E+00 kg _{TSP}	1 h	1000 g _{TSP}	1 g _{TSP uncontrolled}	=	1.9E+00 g _{TSP} / s
1 h	1 blast	3600 s	1 kg _{TSP}	1 g _{TSP}		

Comments
A silica content of: 7.9% was used in the assessment, based on airborne crystalline silica measured on Oct 18,2017 k-factor for TSP (PM44) scaled up logarithmically to 1.13 from published k-factor of 1.0 which refers to PM ₃₀ .
As a conservative simplification, blasting emissions from Reeb Quarry are assumed equivalent to Law Quarry.

APPENDIX B



Appendix B: Processing Emissions Spreadsheet

Law Crushed Stone


Source ID	Source Description / Process Description	AP-42 Process Description	AP-42 Chapter	Processing Rate			Base AP-42 Emission Factor				Base Emission Rate				Additional Control Efficiency Applied (%)	Final Controlled Emission Rate								
				Hourly	Daily	Annual	TSP	PM ₁₀	PM _{2.5}	Silica	TSP	PM ₁₀	PM _{2.5}	Silica		TSP	Data Quality Rating	PM ₁₀	Data Quality Rating	PM _{2.5}	Data Quality Rating	Silica	Data Quality Rating	
				(Mg/h)	(Mg/d)	(Mg/a)	(kg/Mg)	(kg/Mg)	(kg/Mg)	(kg/Mg)	(g/s)	(g/s)	(g/s)	(g/s)		(g/s)	(g/s)	(g/s)	(g/s)	(g/s)	(g/s)	(g/s)	(g/s)	(g/s)
Operations at Working Face & Portable Plant																								
DRILL	Drilling at Working Face	Wet drilling: unfragmented stone	11.19.2-1	2	25	6300	5.7E-05	4.0E-05	6.0E-06		3.3E-05	2.3E-05	3.5E-06		3.3E-05	E	2.3E-05	E	3.5E-06	E	E			
GR	Loader Drop onto Grizzly	Truck unloading - fragmented stone	11.19.2-1	500	5000	800000	1.1E-05	8.0E-06	1.2E-06		1.5E-03	1.1E-03	1.7E-04		1.5E-03	E	1.1E-03	E	1.7E-04	E	E			
CR1	Primary Jaw Crusher	Primary crushing (controlled)	11.19.2-1	500	5000	800000	3.4E-04	2.7E-04	5.0E-05		4.7E-02	3.8E-02	6.9E-03		4.7E-02	E	3.8E-02	E	6.9E-03	E	E			
C01	Conveyor Transfer Point	Conveyor transfer point (controlled)	11.19.2-1	600	6000	960000	3.7E-05	2.3E-05	6.5E-06		6.2E-03	3.8E-03	1.1E-03		6.2E-03	E	3.8E-03	D	1.1E-03	E	D			
SCR	6 X 20 Screen	Screening (controlled)	11.19.2-1	600	6000	960000	5.6E-04	3.7E-04	2.5E-05		9.3E-02	6.2E-02	4.2E-03		9.3E-02	E	6.2E-02	C	4.2E-03	E	C			
CR2	Secondary Cone Crusher	Secondary crushing (controlled)	11.19.2-1	100	1000	160000	3.4E-04	2.7E-04	5.0E-05		9.4E-03	7.5E-03	1.4E-03		9.4E-03	E	7.5E-03	E	1.4E-03	E	E			
C02	Conveyor Transfer Point	Conveyor transfer point (controlled)	11.19.2-1	166	1660	265600	3.7E-05	2.3E-05	6.5E-06		1.7E-03	1.1E-03	3.0E-04		1.7E-03	E	1.1E-03	D	3.0E-04	E	D			
C03	Conveyor Transfer Point	Conveyor transfer point (controlled)	11.19.2-1	166	1660	265600	3.7E-05	2.3E-05	6.5E-06		1.7E-03	1.1E-03	3.0E-04		1.7E-03	E	1.1E-03	D	3.0E-04	E	D			
C04	Conveyor Transfer Point	Conveyor transfer point (controlled)	11.19.2-1	166	1660	265600	3.7E-05	2.3E-05	6.5E-06		1.7E-03	1.1E-03	3.0E-04		1.7E-03	E	1.1E-03	D	3.0E-04	E	D			
ST01	Product Stacker	Conveyor transfer point (controlled)	11.19.2-1	166	1660	265600	3.7E-05	2.3E-05	6.5E-06		1.7E-03	1.1E-03	3.0E-04		1.7E-03	E	1.1E-03	D	3.0E-04	E	D			
C05	Conveyor Transfer Point	Conveyor transfer point (controlled)	11.19.2-1	167	1670	267200	3.7E-05	2.3E-05	6.5E-06	1.8E-06	1.7E-03	1.1E-03	3.0E-04	8.4E-05	1.7E-03	E	1.1E-03	D	3.0E-04	E	8.4E-05			
C06	Conveyor Transfer Point	Conveyor transfer point (controlled)	11.19.2-1	167	1670	267200	3.7E-05	2.3E-05	6.5E-06	1.8E-06	1.7E-03	1.1E-03	3.0E-04	8.4E-05	1.7E-03	E	1.1E-03	D	3.0E-04	E	8.4E-05			
ST02	Product Stacker	Conveyor transfer point (controlled)	11.19.2-1	167	1670	267200	3.7E-05	2.3E-05	6.5E-06	1.8E-06	1.7E-03	1.1E-03	3.0E-04	8.4E-05	1.7E-03	E	1.1E-03	D	3.0E-04	E	8.4E-05			
CT _n	Conveyor Transfer Points (per transfer)	Conveyor transfer point (controlled)	11.19.2-1	167	1670	267200	3.7E-05	2.3E-05	6.5E-06	1.8E-06	1.7E-03	1.1E-03	3.0E-04	8.4E-05	1.7E-03	E	1.1E-03	D	3.0E-04	E	8.4E-05			
Wash Plant																								
WS_C01	Conveyor Transfer Point - Wash station	Conveyor transfer point (controlled)	11.19.2-1	167	1670	267200	3.7E-05	2.3E-05	6.5E-06	1.8E-06	1.7E-03	1.1E-03	3.0E-04	8.4E-05		1.7E-03	E	1.1E-03	D	3.0E-04	E	8.4E-05		
WS_SC1	First Screen at Wash station	Screening (controlled)	11.19.2-1	167	1670	267200	5.6E-04	3.7E-04	2.5E-05	2.9E-05	2.6E-02	1.7E-02	1.2E-03	1.4E-03		2.6E-02	E	1.7E-02	C	1.2E-03	E	1.4E-03		
WS_C02	Conveyor Transfer Point - Wash station	Conveyor transfer point (controlled)	11.19.2-1	84	835	133600	3.7E-05	2.3E-05	6.5E-06	1.8E-06	8.6E-04	5.3E-04	1.5E-04	4.2E-05		8.6E-04	E	5.3E-04	D	1.5E-04	E	4.2E-05		
WS_SC2	Second Screen at Wash station	Screening (controlled)	11.19.2-1	167	1670	267200	5.6E-04	3.7E-04	2.5E-05	2.9E-05	2.6E-02	1.7E-02	1.2E-03	1.4E-03		2.6E-02	E	1.7E-02	C	1.2E-03	E	1.4E-03		
WS_C03	Conveyor Transfer Point - Wash station	Conveyor transfer point (controlled)	11.19.2-1	167	1670	267200	3.7E-05	2.3E-05	6.5E-06	1.8E-06	1.7E-03	1.1E-03	3.0E-04	8.4E-05	100%		E		D		E			
Asphalt Plant Sources (Provided by Miller Paving / Colas Canada)																								
BT1A	transfer - cold feed to conveyor - Coarse	Conveyor transfer point (controlled)	11.19.2-1	41	990	NA	3.7E-05	2.30E-05	6.5E-06	1.8E-06	4.2E-04	2.6E-04	7.4E-05	2.1E-05		4.2E-04	E	2.6E-04	D	7.4E-05	E	2.1E-05		
BT1B	transfer - cold feed bins to conveyor - sand	Conveyor transfer point (controlled)	11.19.2-1	41	990	NA	3.7E-05	2.30E-05	6.5E-06	1.8E-06	4.2E-04	2.6E-04	7.4E-05	2.1E-05		4.2E-04	E	2.6E-04	D	7.4E-05	E	2.1E-05		
BT2	transfer - RAP bins to conveyor	Conveyor transfer point (controlled)	11.19.2-1	22	528	NA	3.7E-05	2.30E-05	6.5E-06	1.8E-06	2.3E-04	1.4E-04	4.0E-05	1.1E-05		2.3E-04	E	1.4E-04	D	4.0E-05	E	1.1E-05		
CT1A	transfer - inclined conveyor to dryer - coarse	Conveyor transfer point (controlled)	11.19.2-1	41	990	NA	3.7E-05	2.30E-05	6.5E-06	1.8E-06	4.2E-04	2.6E-04	7.4E-05	2.1E-05		4.2E-04	E	2.6E-04	D	7.4E-05	E	2.1E-05		
CT1B	transfer - inclined conveyor to dryer - Sand	Conveyor transfer point (controlled)	11.19.2-1	41	990	NA	3.7E-05	2.30E-05	6.5E-06	1.8E-06	4.2E-04	2.6E-04	7.4E-05	2.1E-05		4.2E-04	E	2.6E-04	D	7.4E-05	E	2.1E-05		
CT2	transfer - inclined to batch tower mixer	Conveyor transfer point (controlled)	11.19.2-1	22	528	NA	3.7E-05	2.30E-05	6.5E-06	1.8E-06	2.3E-04	1.4E-04	4.0E-05	1.1E-05		2.3E-04	E	1.4E-04	D	4.0E-05	E	1.1E-05		
SC1A	Screening - Coarse Aggregate	Screening (controlled)	11.19.2-1	41	990	NA	5.6E-04	3.70E-04	2.5E-05	2.9E-05	6.4E-03	4.2E-03	2.9E-04	3.3E-04		6.4E-03	E	4.2E-03	C	2.9E-04	E	3.3E-04		
SC1B	Screening - Sand	Screening (controlled)	11.19.2-1	41	990	NA	5.6E-04	3.70E-04	2.5E-05	2.9E-05	6.4E-03	4.2E-03	2.9E-04	3.3E-04		6.4E-03	E	4.2E-03	C	2.9E-04	E	3.3E-04		
SC2	Screening - RAP	Screening (controlled)	11.19.2-1	22	528	NA	5.6E-04	3.70E-04	2.5E-05	2.9E-05	3.4E-03	2.3E-03	1.5E-04	1.8E-04		3.4E-03	E	2.3E-03	C	1.5E-04	E	1.8E-04		
Reeb Quarry																								
REEB_PR	Total Processing Emissions at Reeb																	1.7E-01		1.2E-01		1.6E-02		3.4E-04

Sample calculation for TSP emissions from Source DRILL: Drilling at Working Face

$$\frac{2 \text{ Mg}_{\text{processed}}}{1 \text{ h}} \times \frac{5.7E-05 \text{ kg}_{\text{TSP}}}{1 \text{ Mg}_{\text{processed}}} \times \frac{1 \text{ h}}{3600 \text{ s}} \times \frac{1000 \text{ g}_{\text{TSP}}}{1 \text{ kg}_{\text{TSP}}} \times \frac{100\% \text{ g}_{\text{TSP uncontrolled}}}{1 \text{ g}_{\text{TSP}}} = 3.3E-05 \text{ g}_{\text{TSP}} / \text{s}$$

Comments
A silica content of: 7.9% was used in the assessment, based on airborne crystalline silica measured on Oct 18, 2017 AP-42 Emission Factor for TSP is based on PM100. The values have been corrected to reflect PM44.
Drilling reflects hole 4 1/2" diameter, 15m deep, assumed density of 2670kg/m ³ , 5 holes / hour Reflects portable plant with 2 product stackers (typical) Screen deck allows for 3 size fractions (including recrush) at a time, thus only 2 stackers are included. Screen is reconfigured when different product sizes needed. Number of Conveyor Transfer points (CT _n) is dependent on configuration and location of portable plant relative to the wash plant
NOx emissions rates were reported for the compliance assessment for the hot mix asphalt plant (ECA number 8-2129-79-987) 24 Hour 3.82E-01 g/s Quality D 1 Hour 7.64E-01 g/s Quality D Assuming 2,640 tonnes/day or 220 tonnes/hour material throughput.
As a conservative assumption, emissions from Reeb Quarry are assumed equivalent to the total emissions from all sources at Law Quarry.

APPENDIX C



Appendix C: Bulk Material Handling Emissions Spreadsheet

Law Crushed Stone

AGGREGATE HANDLING AND STORAGE PILES - AP-42 Section 13.2.4

Average recorded hourly wind speed (m/s):
 (used for sample calculations & factor validation)

Material handling emissions: $E = 0.0016 k (U / 2.2)^{1.3} / (M / 2)^{1.4}$

E emission factor
k particle size multiplier (0.8, 0.74, 0.35 and 0.053 for TSP, PM₃₀, PM₁₀ and PM_{2.5}, respectively) [3]
U mean wind speed, meters per second (m/s)
M material moisture content (%)

Source ID [1]	Description	Processing Rate			Site Data				Base AP-42 Emission Factor				Base Emission Rate				Additional Control Efficiency Applied (%)	Final Controlled Emission Rate at 3.7 m/s							
		Hourly (Mg/h)	Daily (Mg/d)	Annual (Mg/y)	Site Specific Data? (y/n)	Silt Content (%)	Moisture Content (%)	Source Conditions Valid [2]	TSP (kg/Mg)	PM ₁₀ (kg/Mg)	PM _{2.5} (kg/Mg)	Silica (kg/Mg)	TSP (g/s)	PM ₁₀ (g/s)	PM _{2.5} (g/s)	Silica (g/s)		TSP (g/s)	Data Quality Rating	PM ₁₀ (g/s)	Data Quality Rating	PM _{2.5} (g/s)	Data Quality Rating	Silica (g/s)	Data Quality Rating
Operations at Working Face & Portable Plant																									
LOAD1	Product Loading - Stockpiles	266	2656	265600	N	3.9%	2.1%	valid	2.3E-03	1.0E-03	1.6E-04	8.1E-05	1.7E-01	7.6E-02	1.1E-02	6.0E-03		1.7E-01	B	7.6E-02	B	1.1E-02	B	6.0E-03	B
LOAD2	Product Loading - Stockpiles 2	267	2672	267200	N	3.9%	2.1%	valid	2.3E-03	1.0E-03	1.6E-04	8.1E-05	1.7E-01	7.6E-02	1.2E-02	6.0E-03		1.7E-01	B	7.6E-02	B	1.2E-02	B	6.0E-03	B
Wash Plant																									
W_LOAD	Product Loading - Wash station	267	2672	267200	N	3.9%	4.8%	valid	7.4E-04	3.2E-04	4.9E-05	2.6E-05	5.5E-02	2.4E-02	3.6E-03	1.9E-03		5.5E-02	B	2.4E-02	B	3.6E-03	B	1.9E-03	B
W_LOADF	Feed Wash Station	267	2672	267200	N	3.9%	2.1%	valid	2.3E-03	1.0E-03	1.6E-04	8.1E-05	1.7E-01	7.6E-02	1.2E-02	6.0E-03		1.7E-01	B	7.6E-02	B	1.2E-02	B	6.0E-03	B
Asphalt Plant Sources (Provided by Miller Paving / Colas Canada)																									
SP1A	Delivery to stockpile - Coarse Aggregate	41	990			3.9%	4.8%	valid	7.4E-04	3.2E-04	4.9E-05	2.6E-05	8.5E-03	3.7E-03	5.6E-04	2.9E-04		8.5E-03		3.7E-03		5.6E-04		2.9E-04	
SP1B	Delivery to stockpiles - Sand	41	990			3.9%	4.8%	valid	7.4E-04	3.2E-04	4.9E-05	2.6E-05	8.5E-03	3.7E-03	5.6E-04	2.9E-04		8.5E-03		3.7E-03		5.6E-04		2.9E-04	
SP2	Delivery to stockpiles - RAP	22	528			3.9%	4.0%	valid	9.5E-04	4.2E-04	6.3E-05	3.3E-05	5.8E-03	2.5E-03	3.9E-04	2.0E-04		5.8E-03		2.5E-03		3.9E-04		2.0E-04	
B1A	Drop to cold feed bins - Coarse Agg.	41	990			3.9%	4.8%	valid	7.4E-04	3.2E-04	4.9E-05	2.6E-05	8.5E-03	3.7E-03	5.6E-04	2.9E-04		8.5E-03		3.7E-03		5.6E-04		2.9E-04	
B1B	Drop to cold feed bins - Sand	41	990			3.9%	4.8%	valid	7.4E-04	3.2E-04	4.9E-05	2.6E-05	8.5E-03	3.7E-03	5.6E-04	2.9E-04		8.5E-03		3.7E-03		5.6E-04		2.9E-04	
B2	Drop to cold feed bins - RAP	22	528			3.9%	4.0%	valid	9.5E-04	4.2E-04	6.3E-05	3.3E-05	5.8E-03	2.5E-03	3.9E-04	2.0E-04		5.8E-03		2.5E-03		3.9E-04		2.0E-04	
Reeb Quarry																									
REEB_MH	Product Loading at Reeb Quarry																	5.8E-01		2.5E-01		3.8E-02		2.0E-02	

- [1] ID corresponds to process flow diagram for facility and / or material
- [2] Relates to AP-42 Section 13.2.4-4
- [3] k-factor for TSP (PM44) scaled up logarithmically to 0.8 from published k-factor of 0.74 which refers to PM30.

Sample calculation for uncontrolled TSP emission factor for Source LOAD1 : Product Loading - Stockpiles, at a sample wind speed of 3.7 m/s.


$$EF = 0.0016 \times (0.8) \times ((3.7 \text{ m/s}) / 2.2)^{1.3} / ((2.1\%) / 2)^{1.4} = 2.3E-03 \text{ kg TSP / Mg handled}$$

Sample calculation for TSP emission rate for Source LOAD1: Product Loading - Stockpiles, at a sample wind speed of 3.7 m/s.

266 Mg _{handled}	2.3E-03 kg _{TSP}	1 h	1000 g _{TSP}	100% g _{TSP uncontrolled}	=	1.7E-01 g _{TSP} / s
1 h	1 Mg _{handled}	3600 s	1 kg _{TSP}	1 g _{TSP}		

Comments
A silica content of: 7.9% was used in the assessment, based on airborne crystalline silica measured on Oct 18,2017 Shipping is assumed to have a maximum of : 800 tonnes/hour
As a conservative assumption, hourly tonnage reflects total hourly production split between 2 loading spots
Silt and moisture values reflect "various limestone products" on AP-42 Table 13.2.4.-1 After wash plant, moisture content was assumed to be similar to moisture provided in the ECA Number 8-2129-78-087 202 AERMOD Compliance Assessment; 4.8% Moisture content of Coarse Aggregate and Sand 4.0% Moisture content of RAP
As a conservative simplification, emissions from Reeb Quarry are assumed equivalent to the total emissions from all sources at Law Quarry.

APPENDIX D



Appendix D: On-Site Mobile Equipment Emissions Spreadsheet - Fugitive Dust

Project #2202166

Law Crushed Stone

UNPAVED ROAD SECTIONS - AP-42 Section 13.2.2
PAVED ROAD SECTIONS - AP-42 Section 13.2.1

Paved Roads:	$E = k (sL)^{0.91} (W)^{1.02}$
Unpaved Roads - Industrial:	$E = 281.9 k (s / 12)^2 (W / 3)^2$
Unpaved Roads - Public:	$E = 281.9 k (s / 12)^2 (S / 30)^2 / (M / 0.5)^2 - C$

E particulate emission factor (g/VKT)	W average weight of the vehicles traveling the road (US short tons)	M surface material moisture content (%)
k particle size multiplier (see below)	s surface material silt content (%)	S mean vehicle speed (mph)
sL road surface silt loading (g/m ²)	C emission factor for 1980's vehicle fleet exhaust, brake wear and tire wear	a,b,c,d constants (see below)

Route ID [1]	Route Description	Traffic Passes [2]			Segment Length [2] (m)	Road Surface [3]	Roadway Type [4]	Mean Vehicle Speed		Average Vehicle Weight [5] (tons)	Surface Silt Content [7] (%)	Base AP-42 Emission Factor				Base Emission Rate				Additional Control Efficiency Applied (%)	Final Controlled Emission Rate							
		Hourly (#/h)	Daily (#/d)	Annual (#/a)				(km/h)	(mph)			TSP (g/VKT)	PM ₁₀ (g/VKT)	PM _{2.5} (g/VKT)	Silica (g/VKT)	TSP (g/s)	PM ₁₀ (g/s)	PM _{2.5} (g/s)	Silica (g/s)		TSP (g/s)	Data Quality Rating	PM ₁₀ (g/s)	Data Quality Rating	PM _{2.5} (g/s)	Data Quality Rating	Silica (g/s)	Data Quality Rating
Operations at Working Face & Portable Plant																												
LDR	Loader Traffic Muck Pile to Grizzly	69.0	689.7	110345	50	Unpaved	Industrial	20	12	55.8	8.3%	6.2E+03	1.1E+03	1.1E+02	8.9E+01	5.9E+00	1.1E+00	1.1E-01	8.6E-02	95%	3.0E-01	C	5.4E-02	C	5.4E-03	C	4.3E-03	E
LD_01	Loader Traffic at stock pile 1	44.4	444.4	44267	25	Unpaved	Industrial	20	12	40.3	8.3%	5.3E+03	9.8E+02	9.8E+01	7.7E+01	1.6E+00	3.0E-01	3.0E-02	2.4E-02	95%	8.2E-02	C	1.5E-02	C	1.5E-03	C	1.2E-03	E
LD_02	Loader Traffic at stock pile 2	44.4	444.4	44533	25	Unpaved	Industrial	20	12	40.3	8.3%	5.3E+03	9.8E+02	9.8E+01	7.7E+01	1.6E+00	3.0E-01	3.0E-02	2.4E-02	95%	8.2E-02	C	1.5E-02	C	1.5E-03	C	1.2E-03	E
RD_01	Portable Plant Shipping Traffic	25.9	258.6	8586.9	1	Unpaved	Industrial	60	37	45.4	10.0%	6.3E+03	1.2E+03	1.2E+02	9.6E+01	4.5E-02	8.8E-03	8.8E-04	6.9E-04	95%	2.3E-03	C	4.4E-04	C	4.4E-05	C	3.5E-05	E
A_RD_01	Portable Plant Shipping Traffic	25.9	258.6	8586.9	1111	Unpaved	Industrial	60	37	45.4	10.0%	6.3E+03	1.2E+03	1.2E+02	9.6E+01	5.0E+01	9.7E+00	9.7E-01	7.7E-01	95%	2.5E+00	C	4.9E-01	C	4.9E-02	C	3.8E-02	E
B_RD_01	Portable Plant Shipping Traffic	25.9	258.6	8586.9	1197	Unpaved	Industrial	60	37	45.4	10.0%	6.3E+03	1.2E+03	1.2E+02	9.6E+01	5.4E+01	1.0E+01	1.0E+00	8.3E-01	95%	2.7E+00	C	5.2E-01	C	5.2E-02	C	4.1E-02	E
C_RD_01	Portable Plant Shipping Traffic	25.9	258.6	8586.9	1337	Unpaved	Industrial	60	37	45.4	10.0%	6.3E+03	1.2E+03	1.2E+02	9.6E+01	6.0E+01	1.2E+01	1.2E+00	9.2E-01	95%	3.0E+00	C	5.9E-01	C	5.9E-02	C	4.6E-02	E
D_RD_01	Portable Plant Shipping Traffic	25.9	258.6	8586.9	1001	Unpaved	Industrial	60	37	45.4	10.0%	6.3E+03	1.2E+03	1.2E+02	9.6E+01	4.5E+01	8.8E+00	8.8E-01	6.9E-01	95%	2.3E+00	C	4.4E-01	C	4.4E-02	C	3.5E-02	E
Wash Plant																												
W_LDR	Loader Traffic at Wash Pile	44.4	444.4	44533	25	Unpaved	Industrial	20	12	40.3	8.3%	5.3E+03	9.8E+02	9.8E+01	7.7E+01	1.6E+00	3.0E-01	3.0E-02	2.4E-02	95%	8.2E-02	C	1.5E-02	C	1.5E-03	C	1.2E-03	E
W_RD2	Wash Plant Shipping Traffic	13.0	129.7	4306.3	528	Unpaved	Industrial	60	37	45.4	10.0%	6.3E+03	1.2E+03	1.2E+02	9.6E+01	1.2E+01	2.3E+00	2.3E-01	1.8E-01	95%	6.0E-01	C	1.2E-01	C	1.2E-02	C	9.2E-03	E
W_LD1	Loader Traffic Feeding Wash plant	44.4	444.4	44533	25	Unpaved	Industrial	20	12	40.3	8.3%	5.3E+03	9.8E+02	9.8E+01	7.7E+01	1.6E+00	3.0E-01	3.0E-02	2.4E-02	95%	8.2E-02	C	1.5E-02	C	1.5E-03	C	1.2E-03	E
Asphalt Plant Sources (not required for ECA ESDM - added by RWDI)																												
P_SP	Haul Road - delivery to stockpiles	10.7	128.2	8738	394	Unpaved	Industrial	20	12	45.4	10.0%	6.3E+03	1.2E+03	1.2E+02	9.6E+01	3.7E+00	7.1E-01	7.1E-02	5.6E-02	95%	1.8E-01	C	3.6E-02	C	3.6E-03	C	2.8E-03	E
P_HMA	Haul Road - HMA shipping	10.7	128.2	8738	147	Unpaved	Industrial	20	12	45.4	10.0%	6.3E+03	1.2E+03	1.2E+02	9.6E+01	1.4E+00	2.7E-01	2.7E-02	2.1E-02	95%	6.8E-02	C	1.3E-02	C	1.3E-03	C	1.0E-03	E
P_LDR	Loader at Asphalt plant	36.7	440.0	30000	172	Unpaved	Industrial	20	12	40.3	10.0%	6.0E+03	1.2E+03	1.2E+02	9.1E+01	5.2E+00	1.0E+00	1.0E-01	8.0E-02	95%	2.6E-01	C	5.1E-02	C	5.1E-03	C	4.0E-03	E
Reeb Quarry																												
REEB_MF	Mobile Sources at Reeb Quarry																				#####	8.16E-01	8.16E-02	6.44E-02				

Constants for Mobile Emission Equations

Roadway Type	Contaminant	k	a [7]	b [8]	pp [6]	d [6]	Quality
Paved Roads:	PM _{2.5}	0.15	-	-	-	-	-
	PM ₁₀	0.62	-	-	-	-	LD
	PM ₃₀	3.23	-	-	-	-	-
	TSP	4.79	-	-	-	-	-
Unpaved Roads - Industrial:	PM _{2.5}	0.15	0.9	0.45	-	-	C
	PM ₁₀	1.5	0.9	0.45	-	-	B
	PM ₃₀	4.9	0.7	0.45	-	-	B
	TSP	7.32	0.6	0.45	-	-	C
Unpaved Roads - Public:	PM _{2.5}	0.18	1	-	0.2	0.5	C
	PM ₁₀	1.8	1	-	0.2	0.5	B
	PM ₃₀	6	1	-	0.3	0.3	B
	TSP	8.96	1	-	0.49	0.2	C

- [1] Route ID numbers provided on site plan.
- [2] Length of a specific road segment. A separate segment should be used whenever one or more parameters change.
- [3] Paved surfaces include asphalt, concrete, and recycled asphalt (if it forms a relatively consistent surface).
- [4] Publicly accessible and dominated by light vehicles, or industrial, and dominated by heavy vehicles.
- [5] The average vehicle weight reflects the average of the empty and loaded vehicle weight, for travel in both directions.
- [6] Required only for publicly accessible unpaved roads.
- [7] Required only for unpaved roads (public and industrial).
- [8] Required only for industrial paved roads.

Sample calculation for uncontrolled TSP emission factor for Source LDR: Loader Traffic Muck Pile to Grizzly

$$EF = 281.9 \times (4.9) \times [(8.3\% / 12)]^{0.7} \times [(55.8 \text{ tons}) / 3]^{1.02} = 6163 \text{ g TSP / vehicle kilometer travelled (vkt)}$$


Sample calculation for TSP emission rate for Source LDR: Loader Traffic Muck Pile to Grizzly

69 vehicles	50 m	1 km	6163 g _{TSP}	1 h	0.05 g _{TSP uncontrolled}
1 h		1000 m	1 vehicle km	3600 s	1 g _{TSP}

= 2.95E-01 g_{TSP} / s

Comments
A silica content of: 7.9% was used in the assessment, based on airborne crystalline silica measured on Oct 18, 2017
Constants for TSP (PM44) extrapolated from published factors for PM30, PM10 and PM2.5. Data quality downgraded by one step.
Current working face loader Cat 988B, stock pile, wash plant and asphalt plant Cat 980H
Loader at working face (1) is a single Cat 988B (43.36Mg tare, 14.5Mg payload from Caterpillar specs)
Loaders at plant (2) are Cat 980H (30.52Mg tare, 12Mg payload, from Caterpillar specs)
It is assumed that the average fleet will be similar make of " 3-axle Truck and 4-axle Full Trailer, Aggregate Vehicle"
- Tare weight on average set to 21 tonnes, payload weight set to 41 tonnes (Gross Weight 62 tonnes)
Silt loading for haul rounds assumed 2X that from AP-42 Table 13.2.1-3, to account for some amount of potential dragout from the site.
Hourly and Daily traffic based off max 800 tonnes/hour shipping for 10 hours a day.
Annual traffic passes based on licence limits (800,000 tonnes/year)
Asphalt plant emissions based off of 2640 tonnes/day and 180000 tonnes/year
As a conservative assumption, emissions from Reeb Quarry are assumed equivalent to the total emissions from all sources at Law Quarry. (Route C_RD_01 used for shipping traffic).

APPENDIX E



Appendix E: Summary of Combustion Exhaust Emissions (Mobile and Stationary Sources)

Law Crushed Stone

Source ID	Description	Gross Power Rating (kW)	Number Of Units	Traffic Passes [2]		Segment Length [3] (m)	Mean Vehicle Speed (km/h)	Load Factor [4] (%)	Tailpipe Emission Factor [5]								Tailpipe Emission Rate				Tailpipe + Fugitive Emission Rate [6]			
				Hourly (#/h)	Daily (#/d)				TSP		PM10		PM2.5		NOx		TSP (g/s)	PM10 (g/s)	PM2.5 (g/s)	NOx (g/s)	TSP (g/s)	PM10 (g/s)	PM2.5 (g/s)	NOx (g/s)
									(g/vkt)	(g/kW-h)	(g/vkt)	(g/kW-h)	(g/vkt)	(g/kW-h)	(g/vkt)	(g/kW-h)								
Operations at Working Face & Portable Plant																								
LDR	Loader Traffic Muck Pile to Grizzly	280	1	69.0	689.7	50	20	53%	--	0.02	--	0.02	--	0.02	--	6.6	8.2E-04	8.2E-04	8.2E-04	2.7E-01	3.0E-01	5.5E-02	6.2E-03	2.7E-01
LD_01	Loader Traffic at stock pile 1	260	1	44.4	444.4	25	20	53%	--	0.02	--	0.02	--	0.02	--	6.6	7.7E-04	7.7E-04	7.7E-04	2.5E-01	8.3E-02	1.6E-02	2.3E-03	2.5E-01
LD_02	Loader Traffic at stock pile 2	260	1	44.4	444.4	25	20	53%	--	0.02	--	0.02	--	0.02	--	6.6	7.7E-04	7.7E-04	7.7E-04	2.5E-01	8.3E-02	1.6E-02	2.3E-03	2.5E-01
RD_01	Portable Plant Shipping Traffic	n/a	n/a	25.9	258.6	1	60	n/a	0.83	--	0.83	--	0.83	--	6.98	--	6.0E-06	6.0E-06	6.0E-06	5.0E-05	2.3E-03	4.4E-04	5.0E-05	5.0E-05
A_RD_01	Portable Plant Shipping Traffic	n/a	n/a	25.9	258.6	1111	60	n/a	0.83	--	0.83	--	0.83	--	6.98	--	6.6E-03	6.6E-03	6.6E-03	5.6E-02	2.5E+00	4.9E-01	5.5E-02	5.6E-02
B_RD_01	Portable Plant Shipping Traffic	n/a	n/a	25.9	258.6	1197	60	n/a	0.83	--	0.83	--	0.83	--	6.98	--	7.1E-03	7.1E-03	7.1E-03	6.0E-02	2.7E+00	5.3E-01	6.0E-02	6.0E-02
C_RD_01	Portable Plant Shipping Traffic	n/a	n/a	25.9	258.6	1337	60	n/a	0.83	--	0.83	--	0.83	--	6.98	--	8.0E-03	8.0E-03	8.0E-03	6.7E-02	3.0E+00	5.9E-01	6.7E-02	6.7E-02
D_RD_01	Portable Plant Shipping Traffic	n/a	n/a	25.9	258.6	1001	60	n/a	0.83	--	0.83	--	0.83	--	6.98	--	6.0E-03	6.0E-03	6.0E-03	5.0E-02	2.3E+00	4.4E-01	5.0E-02	5.0E-02
Wash Plant																								
W_LDR	Loader Traffic at Wash Pile	260	1	44.4	444.4	25	20	53%	--	0.02	--	0.02	--	0.02	--	6.6	7.7E-04	7.7E-04	7.7E-04	2.5E-01	8.3E-02	1.6E-02	2.3E-03	2.5E-01
W_RD2	Wash Plant Shipping Traffic	n/a	n/a	13.0	129.7	528	60	n/a	0.83	--	0.83	--	0.83	--	6.98	--	1.6E-03	1.6E-03	1.6E-03	1.3E-02	6.0E-01	1.18E-01	1.32E-02	1.3E-02
W_LD1	Loader Traffic Feeding Wash plant	260	1	44.4	444.4	25	20	53%	--	0.02	--	0.02	--	0.02	--	6.6	7.7E-04	7.7E-04	7.7E-04	2.5E-01	8.3E-02	1.6E-02	2.3E-03	2.5E-01
Asphalt Plant Sources (not required for ECA ESDM - added by RWDI)																								
P_SP	Haul Road - delivery to stockpiles	n/a	n/a	10.7	128.2	394	20	53%	0.83	--	0.83	--	0.83	--	6.98	--	4.8E-04	4.8E-04	4.8E-04	8.2E-03	1.8E-01	3.6E-02	4.0E-03	8.2E-03
P_HMA	Haul Road - HMA shipping	n/a	n/a	10.7	128.2	147	20	53%	0.83	--	0.83	--	0.83	--	6.98	--	1.8E-04	1.8E-04	1.8E-04	3.0E-03	6.8E-02	1.3E-02	1.5E-03	3.0E-03
P_LDR	Loader at Asphalt plant	260	1	36.7	440.0	172	20	53%	--	0.02	--	0.02	--	0.02	--	6.6	7.7E-04	7.7E-04	7.7E-04	2.5E-01	2.6E-01	5.1E-02	5.8E-03	2.53E-01
Stationary Combustion Equipment																								
GEN	Portable Plant Generator Set	609	1	n/a	n/a	n/a	n/a	100%	--	0.63	--	0.63	--	0.63	--	6.4	1.1E-01	1.1E-01	1.1E-01	1.1E+00	1.1E-01	1.1E-01	1.1E-01	1.1E+00
Reeb Quarry																								
REEB_MB	Mobile Sources at Reeb Quarry																1.20E-01	1.20E-01	1.20E-01	2.45E+00	4.36E+00	9.36E-01	2.02E-01	2.45E+00

- [1] ID should reflect Source ID or Route ID, as appropriate.
- [2] Where applicable, this value reflects travel in both directions (e.g., 1 round-trip = 2 passes)
- [3] Length of a specific road segment. A separate segment should be used whenever one or more parameters change.
- [4] Load Factors from "Median Life, Annual Activity, and Load Factor Values for Nonroad Engine Emissions Modeling", EPA-420-R-10-016, NR-005d, July 2010
- [5] Emissions are input on either a vehicle distance or power rating basis. Load factor applies only to emissions based on power ratings.
- [6] Applicable only for TSP, PM10 and PM2.5 emissions from mobile equipment. Emissions rates for NOx and stationary sources do not change.

Sample Calculations

Pit Loader Exhaust TSP Emissions:


$$\frac{280 \text{ kW}}{1 \text{ kW h}} \times \frac{0.02 \text{ g}}{1 \text{ kW h}} \times \frac{53\% \text{ Load}}{1 \text{ kW h}} \times \frac{1 \text{ h}}{3600 \text{ s}} = 1.0\text{E-}03 \text{ g}_{\text{TSP}} / \text{s}$$

Truck Exhaust TSP from Wash Station:(10 Rd East)

$$\frac{13.0 \text{ Vehicles}}{1 \text{ h}} \times \frac{528 \text{ m}}{1 \text{ h}} \times \frac{0.83 \text{ g}}{1 \text{ Veh. Km}} \times \frac{1 \text{ km}}{1000 \text{ m}} \times \frac{1 \text{ h}}{3600 \text{ s}} = 1.6\text{E-}03 \text{ g}_{\text{TSP}} / \text{s}$$

Comments	
Emission factor from highway trucks based on U.S. EPA MOVES model at relevant speed for roadway segment.	
Factors reflect highest of early morning, mid-day, and late-afternoon emission estimates provided by MOVES.	
Working face loader rating based on Cat 988B Loader (www.ritchiespecs.com), Tier 2	
Plant loader rating based on Cat 980H Loader (www.ritchiespecs.com), Tier 1	
TSP (and PM2.5 emissions for loaders and generator sets) assumed to be equal to PM10 emissions.	
Generator set engine (Cat 3412, 817hp) specification sheet provided by Toromont Tech Services.	
Generator emissions were updated to reflect Tier 2 standards.	
Generator exhaust data: 892.4°F, 4,626.23 cfm	478 °C 751 K
	2.18 m³/s
Assume stack exit diameter of 12"	0.30 m
	30.8 m/s
Hourly and Daily traffic based on max 800 tonnes/hour shipping for 10 hours a day.	
Annual traffic passes based on license limits (800,000 tonnes/year)	
PM from Asphalt plant emissions based on 2640 tonnes/day	
NOx from Asphalt plant based on 220 tonnes/hour (conservative)	
Emissions from Reeb Quarry were conservatively assumed to be equivalent to the total emissions from all sources at Law Quarry (Route C_RD_01 used for shipping traffic).	

APPENDIX F



Appendix F: Summary of Additional Emissions from Asphalt Plant

Law Crushed Stone Project # 2202166

Volume Sources

Modelling Source ID	Modelling Source Description	Emission Rate (g/s)				
		TSP (24H)	PM ₁₀ (24H)	PM _{2.5} (24H)	NO _x (24H)	NO _x (1H)
H1	Hot Oil heater	0	0	0	2.35E-02	2.35E-02
ACTANKS	Asphalt Cement Storage Tanks	1.59E-04	1.59E-04	1.59E-04	0	0
SF1	HMA Silo Filling	6.41E-03	6.41E-03	6.41E-03	0	0
SF2	HMA Silo Filling	6.41E-03	6.41E-03	6.41E-03	0	0
SL1	HMA truck loadout from HMA silos	6.59E-03	6.59E-03	6.59E-03	0	0
SL2	HMA truck loadout from HMA silos	6.59E-03	6.59E-03	6.59E-03	0	0
BL	HMA truck loadout from batch tower	1.32E-02	1.32E-02	1.32E-02	0	0

Point Sources

Modelling Source ID	Modelling Source Description	Emission Rate (g/s)				
		TSP (24H)	PM ₁₀ (24H)	PM _{2.5} (24H)	NO _x (24H)	NO _x (1H)
BH	Baghouse.servicing the HMA plant including the Natural gas-fired dryer/mixing	6.42E-01	6.42E-01	6.42E-01	3.82E-01	7.64E-01

Comments
<p>Emissions were obtained from compliance assessment for the hot mix asphalt plant (ECA number 8-2129-79-987)</p> <p>Emissions that were dependent on wind speeds were modelled alongside of wind erosion or handling</p> <p>Emissions that needed size distribution are displayed in Processing and Handling to calculate</p> <p>All asphalt plant emissions were reduced to 25% in Winter (Jan, Feb, March) based on the compliance assessment for the hot mix asphalt plant (ECA number 8-2129-79-987)</p>